



***Project
Development
and
Environment
(PD&E) Study***

Final Pond Siting Report

***S.R. 574 (Martin Luther King Jr. Boulevard)
from C.R. 579 to McIntosh Road
Hillsborough County, Florida***

**WPI Segment No. 255893 1
FAP No. 2081-018P**



**Florida Department of Transportation - District 7
Tampa, Florida**

July 2002



Florida Department of Transportation
Project Development and Environment (PD&E) Study

Final Pond Siting Report

**S.R. 574 (Martin Luther King Jr. Boulevard)
from C.R. 579 to McIntosh Road
Hillsborough County, Florida**

**WPI Segment No.: 255893 1
FAP No. 2081-018P**

Submitted to:

**Florida Department of Transportation - District 7
Tampa, Florida**

Submitted by:

AYRES
ASSOCIATES

July 2002

TABLE OF CONTENTS

<u>SECTION</u>		<u>PAGE</u>
	TABLE OF CONTENTS	i
	APPENDICES	i
	LIST OF TABLES	ii
	LIST OF FIGURES	ii
1.0	INTRODUCTION.....	1
2.0	PROJECT DESCRIPTION	2
2.1	Existing Drainage Patterns	3
2.2	Soils Information	4
2.3	Wetlands and Threatened and Endangered Species	5
2.4	Floodplains	7
3.0	POND SITING ANALYSIS	9
3.1	Drainage Approach and Development of Alternative Pond Sites	9
3.2	Evaluation of Alternative Pond Sites	12
4.0	PERMIT REQUIREMENTS	14
5.0	RECOMMENDATIONS.....	15
APPENDICES		
Appendix A	Hydraulic Calculations	
Appendix B	Plan Sheet Exhibits	
Appendix C	Right-of-way Costs	
Appendix D	Construction Costs	

LIST OF TABLES

<u>TABLE NO.</u>	<u>PAGE</u>
2-1 Tampa Bypass Canal Watershed	4
2-2 Baker Canal Watershed	4
3-1 Drainage Sub-Basin Characteristics	10
3-2 Summary of Proposed Pond Site Characteristics	11
3-3 Right-of-way and Construction Costs for Proposed Pond Locations	13

LIST OF FIGURES

<u>FIGURE NO.</u>	<u>FOLLOWS PAGE</u>
2-1 General Project Location Map	2
2-2 Recommended Alternative 5-Lane Urban Roadway Typical Section	2
2-3 Recommended Alternative 4-Lane Suburban Roadway Typical Section (45 mph Design Speed)	2
2-4 Recommended Alternative 4-Lane Suburban Roadway Typical Section (60 mph Design Speed)	2
2-5 4-Lane Bridge Typical Section (Bridge Replacement Alternative)	2
2-6 Drainage Basins	3

1.0 INTRODUCTION

The Florida Department of Transportation (FDOT) is conducting a Project Development and Environment (PD&E) Study to document the preliminary engineering concept for improvements to S.R. 574 (Martin Luther King Jr. Boulevard) from C.R. 579 (Mango Road) to east of McIntosh Road in central Hillsborough County. The length of the Study corridor is approximately 3.6 miles. The purpose of the PD&E Study is to provide environmental and engineering information, as well as the analyses necessary for the FDOT and the Federal Highway Administration (FHWA) to reach a decision regarding the type, design and location of the improvements to S.R. 574; and the impacts, if any, associated with the project.

This Pond Siting Report (PSR) is prepared to find and assess suitable land areas for storm water management and floodplain compensation ponds, using the following criteria: economic feasibility, federal and state protected species, hazardous materials, archaeological resources, utility corridors and easements, geological and hydrologic characteristics, current and proposed land uses, wildlife corridors, and drainage design considerations. Two alternative pond sites are identified and evaluated for each drainage basin, and an optimal site is recommended. It should be noted that information from the following separate technical memorandums of this Study was used for the PSR: Design High Water Report, Preliminary Bridge Analysis, and the Location Hydraulic Report.

PROJECT DESCRIPTION

Within the S.R. 574 corridor, S.R. 574 is an east/west urban minor arterial. The limits of the Study corridor are from C.R. 579 (Mango Road) to McIntosh Road, a distance of approximately 3.6 miles. The project is located in central Hillsborough County and extends through the communities of Mango, Seffner and Dover. A project location map is shown in Figure 2-1.


The existing land use adjacent to the S.R. 574 corridor transitions through two areas of generalized land use characteristics. From the western terminus eastward, the land uses transition from dense development (medium scale shopping centers, office/professional office, medical facilities, service stations, restaurants and community facilities) to low density development (a mixture of agricultural, commercial, and planned and residential developments). Although vacant land exists within the Study corridor, future developments are planned for most of this area.


S.R. 574 is currently a six-lane urban section at C.R. 579, which transitions to a three-lane rural section (with a two-way left-turn lane) east of Highview Road. The three-lane section continues to Kingsway Road, where the roadway transitions to a two-lane section up to McIntosh Road. The existing posted speed limits along S.R. 574 are 45 mph and 50 mph.

The recommended alternative for the multi-laning of S.R. 574 from C.R. 579 to east of McIntosh Road can be described with three typical roadway sections. The portion of the project between C.R. 579 and east of Parsons Avenue is proposed to be widened to a 5-lane urban typical section (40 mph design speed) that includes a two-way left turn lane. A 4-lane suburban typical section (45 mph design speed) is proposed in the portion of the project from east of Parsons Avenue to east of Kingsway Avenue. The remaining portion of the project from east of Kingsway Road to east of McIntosh Road is proposed to be a 4-lane suburban typical (60 mph design speed). Both 4-lane suburban typical sections can be expanded to 6-lanes, and the right-of-way (ROW) requirements are 123.5 feet and 131.5 feet for the 45 mph and 60 mph design speeds, respectively. Figures 2-2 through 2-4 illustrate the recommended alternative typical sections.

The recommended alignment generally follows the existing centerline of the roadway with some realignment to reduce impacts to established commercial properties and to avoid a historical cemetery in the western portion of the project. The recommended alignment for the eastern portion of the project was based on a 25-foot offset from the proposed ROW line to the centerline of the existing, active CSX railroad track.

This project also contains one bridge, which spans Baker Canal and is located in the existing two-lane section of the project west of Valrico Road (Figure 2-5 provides the typical sections of the existing bridge and the bridge replacement alternative).






HIGHVIEW ROAD TO PARSONS AVENUE **(40 MPH DESIGN SPEED)**



S.R. 574 (Martin Luther King Jr. Blvd.)
 Project Development & Environment (PD&E) Study
 Hillsborough County, Florida
 WPI Segment No. 255893 1
 FAP No. 2081-018P

RECOMMENDED ALTERNATIVE
5 - LANE URBAN ROADWAY
TYPICAL SECTION

Figure 2-2




PARSONS AVENUE TO KINGSWAY ROAD (45 MPH DESIGN SPEED)



S.R. 574 (Martin Luther King Jr. Blvd.)
Project Development & Environment (PD&E) Study
Hillsborough County, Florida
WPI Segment No. 255893 1
FAP No. 2081-018P

**RECOMMENDED ALTERNATIVE
4 - LANE SUBURBAN ROADWAY
TYPICAL SECTION**

Figure 2-3




KINGSWAY ROAD TO McINTOSH ROAD (60 MPH DESIGN SPEED)



S.R. 574 (Martin Luther King Jr. Blvd.)
Project Development & Environment (PD&E) Study
Hillsborough County, Florida
WPI Segment No. 255893 1
FAP No. 2081-018P

**RECOMMENDED ALTERNATIVE
4 - LANE SUBURBAN ROADWAY
TYPICAL SECTION**

Figure 2-4



BAKER CANAL



S.R. 574 (Martin Luther King Jr. Blvd.)
 Project Development & Environment (PD&E) Study
 Hillsborough County, Florida
 WPI Segment No. 255893 1
 FAP No. 2081-018P

4 - LANE BRIDGE TYPICAL SECTION (BRIDGE REPLACEMENT ALTERNATIVE)

Figure 2-5

2.1 Existing Drainage Patterns

The existing drainage patterns and basin limits were developed utilizing USGS quadrangle maps, SWFWMD contour aerial photography, data collected during field visits and existing drainage studies (*Hillsborough County Stormwater Management Master Plan* and *Hillsborough River Watershed Management Plan*).


The limits of the Study corridor lie within two significant watersheds. From the beginning of the corridor eastward to Parsons Avenue, the project is part of the Tampa Bypass Canal Watershed (portion of the Hillsborough River Watershed). From Parsons Avenue eastward to the end of the corridor, the project is part of the Pemberton Creek/Baker Canal Watershed.

The Tampa Bypass Canal is a wide trapezoidal channel, and a regulated floodway that contains six major control structures operated by SWFWMD. The total watershed area served by the canal is 45.9 square miles, and the sub-watershed that contains the corridor is identified as "Mango," which has a drainage area of 9.1 square miles. This sub-watershed originates at Lake Mango and flows through a main drainage ditch westward to the bypass canal. The open basins within this portion of the Study corridor ultimately discharge via this ditch system to the Tampa Bypass Canal. The closed basins within the Study corridor do not outfall to the Tampa Bypass Canal unless significant flooding and overtopping of the nearby CSX railroad tracks, to the south, occur.

The Pemberton Creek/Baker Canal (PBA) Watershed is 65.0 square miles in size, and contains six major conveyance systems and one outfall. The six conveyance systems are Flint Creek, Campbell Branch, Antioch Branch, Baker Creek, Pemberton Creek, and Baker Canal. Baker Creek receives storm water from the convergence of Pemberton Creek and Baker Canal, and flows one-mile northward into Lake Thonotosassa. This lake is the largest lake in Hillsborough County with a surface area of 819-acres and an average depth of 11.5 feet. The lake outfalls through a control structure operated by SWFWMD into Flint Creek, which flows northward to the Hillsborough River.

The corridor is located in the Baker Canal sub-watershed, which is the southernmost sub-watershed in the PBA system (Pemberton Creek is north of this sub-watershed and east of Lake Thonotosassa, and originates in Plant City six-miles away). Baker Canal originates in Dover, east of the corridor, and flows westward to Lake Hooker. This lake receives storm water from two interconnected lakes to the south, Valrico Lake and Long Pond, and then discharges northward through two crossings beneath S.R. 574. The western most crossing proceeds to nearby Lake Weeks through a triple concrete pipe culvert, and Baker Canal crosses nearby through a bridge opening. The outfall of Lake Weeks connects to Baker Canal north of the corridor, and the canal then continues to the before-mentioned convergence with Pemberton Creek and ultimately to Lake Thonotosassa.

Figure 2-6 depicts the water shed and basin boundaries as well as the existing drainage patterns within the Study area. Tables 2-1 and 2-2 summarize the specific basin data (the basin numbers in the tables correspond to those shown



S.R. 574 (Martin Luther King Jr. Blvd.)
 Project Development & Environment (PD&E) Study
 Hillsborough County, Florida
 WPI Segment No. 255893 1
 FAP No. 2081-018P

DRAINAGE BASINS

Figure 2-6

in the Figure), which are from the *Hillsborough River Watershed Management Plan*.

1-1: Tampa Bypass Canal Watershed

Basin Number	Corresponding Study ID Number	25-Year DHW Elevation (Feet)	100-Year DHW Elevation (Feet)	Open/Closed	Sub Basin Area (Acres)	TOC (min.)	CN
	615450	40.91	42.73	Closed	107.75	44.53	86.01
	615660	-----	-----	Closed	151.95	60.00	81.62
5	615500	44.33	45.24	Open	128.72	86.29	79.71

2-2: Baker Canal Watershed

Basin Number	Corresponding Study ID Number	25-Year DHW Elevation (Feet)	100-Year DHW Elevation (Feet)	Open/Closed	Sub Basin Area (Acres)	TOC (min.)	CN
	0311007	70.62	71.53	Open	50.90	29.00	74.00
	0309790	64.90	66.22	Closed	67.80	34.00	67.00
	0309800	46.86	47.42	Open	299.60	41.00	73.00
	0309596	46.26	47.32	Open	181.50	68.00	80.00
	0309650	46.26	47.32	Open	75.20	42.00	81.00
	0309680	58.22	58.41	Open	17.60	44.00	71.00
	0310075	58.48	58.90	Open	51.90	57.00	72.00
	0310060	48.52	49.90	Open	124.10	85.00	77.00
	0310002	47.38	48.85	Open	28.70	53.00	80.00
	0311000	47.45	48.97	Open	887.50	148.00	80.00
	0311003	72.33	72.40	Open	29.90	61.00	57.00
	0311005	66.79	67.66	Open	96.20	29.00	63.00

Soils Information

The USDA's *Soil Survey of Hillsborough County, Florida* and field reconnaissance were used to identify the soil types within the Study corridor. In general, soils are sandy and range from poorly drained to excessively drained depending on elevation.

The Adamsville, Basinger, Myakka, Ona, St. Johns and Seffner soil series represent the portion of the soils within the Study corridor that are poorly drained with seasonal high groundwater levels varying from 2 feet above the existing ground surface to 3.5 feet below the existing surface. These soil types are typically encountered on broad plains on the flatwoods and in swamps and

depressions and along the drainage ways of the flatwoods. For this Study, it is anticipated that these soil types would be present between Lenna Avenue and Shady Acres Road.

The remaining soil types within the Study corridor consist of Candler, Gainesville, Lake and Orsino Series. These soil types are moderately to excessively drained with seasonal high groundwater elevations varying from 3.5 feet to 5 feet deep to in excess of 6 feet below the existing ground surface. It should be noted that within the urban portion of the project debris as well as unsuitable material may be encountered.

As part of the preliminary investigation, a preliminary sinkhole/ground subsidence evaluation was conducted that consisted of field reconnaissance of the proposed roadway alignment as well as a study of available published data and field investigation information. Based on the data available, it was concluded that there was no evidence of sinkhole activity along the Study corridor; however, it should be noted that the ecological and hydrogeologic conditions within the Study corridor could potentially result in the development of sinkholes.

Wetlands and Threatened and Endangered Species

Wetlands within the corridor were initially identified through review of mapping resources including the Natural Resources Conservation Service's (formerly the Soil Conservation Service) *Soil Survey of Hillsborough County, Florida (1989)*, National Wetland Inventory mapping, and 1 inch = 200 feet scale project aerial photography, which was documented in this Study's *Draft Wetland Evaluation Report*. Wetlands were identified in the field utilizing the United State Army Corps of Engineer's (USACOE's) *Federal Manual for Identifying and Delineating Jurisdictional Wetlands (1987)*. The wetlands were classified according to the United States Fish and Wildlife Service methodology; and wetlands that may be potentially affected were assessed for functional significance using the Wetland Rapid Assessment Procedure (WRAP), as developed by the South Florida Water Management District (SFWMD) and utilized by the USACOE. Sizes of potential wetland impacts were determined graphically from project aerial photographs and project concept plans.

The surface water systems are incised urban creeks within the S.R. 574 right-of-way that were natural in origin; however, they have been altered to function primarily for flood control. The natural systems in the project right-of-way are either connected to existing storm water management systems or isolated in nature.

Eight wetlands and natural surface waters and thirty other surface waters were identified within and along the project corridor. Wetland Rapid Assessment Procedure (WRAP) analyses were conducted for the eight wetlands and natural surface waters. These areas consisted primarily of scrub-shrub palustrine systems, palustrine systems with emergent vegetation, and palustrine systems with an unconsolidated bottom. The highest rated wetland, a palustrine scrub/shrub system, received a WRAP score of 0.58.

Additionally, the Study area was evaluated for the potential of affecting designated "critical habitat" as defined by the USFWS. No "critical habitat" designated for listed species occurs within the project corridor.

Four avian species listed as Species of Special Concern by the FWC were observed in wetlands along the corridor: little blue heron, snowy egret, white ibis, and brown pelican. In addition, one avian species listed as Endangered by the USFWS and FWC, the wood stork, was observed in a wetland within the project corridor. The presence of these species should not be a concern because they are highly mobile in nature.

As a result of the urban nature of the Study corridor, and according to a literature search (FNAI, FWC and USFWS databases for Hillsborough County) and field surveys, it was determined that no threatened and/or endangered species are expected to be adversely affected by the project. Informal consultation has been initiated with the USFWS and a no effect determination is anticipated.

Floodplains

The corridor's floodplains are narrow areas associated with the slight overtopping of two man-made drainage channels, Lake Weeks Creek and Baker Canal, which traverse S.R. 574. These floodplains are bordered by low-density commercial and residential property and the CSX railroad. Although the channels provide important storm water conveyance, the floodplains beyond the channels do not provide any of the following benefits due to their small areas and their low frequency of inundation: water quality, groundwater recharge, wildlife habitat, natural beauty, recreation, agriculture, aquaculture or forestry. Constructing a longer culvert at Lake Weeks Creek and a wider bridge at Baker Canal will cause small impacts to these floodplains. Since these floodplains are associated with conveyance and not storage, mitigation for these impacts will be provided by demonstrating hydraulic equivalency for the two crossings in a 100-year storm event (no storm water attenuation should be required to compensate for the filled areas). Best management practices should be implemented during construction and maintenance to prevent erosion and siltation. Wetland impacts would be within man-made ditches, and to wetlands of marginal quality that contain nuisance plant species and do not provide adequate wildlife habitats. Therefore, wetland mitigation is not expected to be required for the impacts within the floodplains that will be caused by the improved channel crossings.

The portion of the corridor from C.R. 579 to Parsons Avenue either drains westward to a large borrow pit, or to a self-contained french drain system. Since no large offsite areas drain to or across S.R. 574 there are no cross culverts that need to be evaluated; and though no 100-year flood zones are identified by FEMA mapping, storm water management facilities will need to be provided. These facilities are required to attenuate the storm water runoff from the additional pavement area of the build alternative. Due to the generally closed nature of the sub-basins this attenuation requirement should be based on a 100-year storm event. This is due to the CSX railroad isolating the corridor from the main drainage ditch of the Mango sub-watershed.

The portion of the corridor from Parsons Avenue to Kingsway Avenue also contains french drains, but instead of being self-contained they have a means of discharging when the storm water reaches a high stage within the drains. This storm water proceeds to Lake Weeks Creek, which outfalls ultimately to Lake Thonotosassa and the Hillsborough River. Therefore, attenuation does not need to be based on the 100-year storm event but can be conceptually designed to the 25-year event; and storm water treatment is anticipated to be provided by extended wet detention due to the lower elevations in the eastern portion of the project and proximity to the groundwater table. Conceptual drainage design for the portion of the corridor from Kingsway Avenue to beyond McIntosh Road would use this same approach, and would outfall to Lake Weeks Creek or the Baker Canal depending on the location of the drainage segment. There are two segments within this portion of the corridor that drain to large existing ditches that provide attenuation as well as conveyance, a 700' segment on the north-side of S.R. 574 and east of Kingsway Avenue and a 3,600' segment on the north side of S.R. 574 between Valrico Road and McIntosh Road. These basins will need to be conceptually designed to include compensation for lost ditch volume in addition to the difference in runoff from a 25-year storm event.

3.0 POND SITING ANALYSIS

3.1 Drainage Approach and Development of Alternative Pond Sites

The Study corridor exists in two major watersheds and the existing high-points, as well as bridge #100033 and two existing cross culverts, divide the project area into nine basins (refer to Section 2.1). These basin boundaries were in turn utilized to develop potential pond sites and to determine the anticipated storm water attenuation and treatment needs of each pond site.

The conceptual drainage design consists of constructing attenuation ponds to accommodate the additional runoff from the increased impervious areas of the build alternatives. The attenuation requirements are based on retaining the pre-construction/post-construction runoff volume difference in a 100-year, 10-day storm event (23.0 inches of rainfall) for the project's basins that are closed. This approach is used for the beginning portion of the project and proceeds eastward to Parsons Avenue. A portion of the project east of McIntosh Road, though not a closed basin, must also provide compensation for lost ditch volume. In the portion of the project that begins east of Parsons Avenue, the basins drain toward Baker Canal and are considered to be open. The attenuation requirements for the ponds that are conceptually designed in this area of the Study, are based on detaining the pre-construction/post-construction peak runoff rate difference in a 25-year, 24-hour storm event (8.2 inches of rainfall).

Storm water treatment will meet SWFWMD criteria, and the conceptual design considers online treatment to avoid multiple cells or multiple ponds (this approach will be refined in the separate design phase). The treatment volume required is thus the runoff resulting from 1" of rainfall over the total impervious area of the build alternative. Depending on the depth of the storm water pond, the pond area that is required for each drainage segment of the corridor will be controlled by either the treatment volume or the attenuation volume. It is expected that most of the ponds will utilize extended wet detention for the treatment method, except for the higher portion of the corridor around Parsons Avenue. The treatment volume in the pond is based on a maximum depth of 18" above the control elevation, which is the estimated SHW elevation at the pond's outfall.

The conceptual ponds considered in the basins were sized utilizing the SCS Runoff Curve Number Method presented in the United States Department of Agriculture Publication, *Urban Hydrology for Small Watersheds*. The attenuation volume of the ponds within a closed basin (100-year, 10-day storm event) was calculated by averaging the top of pond elevation and the bottom of pond elevation and applying the depth of the pond. The attenuation volume of the ponds within an open basin (25-year, 24-hour storm event) was determined utilizing the same methodology, except that one foot of freeboard was included in the calculations. The pond bottoms were established based on the lowest existing ground elevation within the parcels under consideration. This is a conservative approach to allow sufficient clearance from the water table, but still provides 6 to 7 feet of pond depth due to the existing ground slopes within the parcels (pond berms were applied as needed). The pond cross section was

established utilizing the following criteria: 2:1 slope between existing property lines and the top-of-berms, berm widths of 20 feet for maintenance purposes, and a 4:1 slope between the top-of-berm and the bottom-of-pond.

Table 3-1 provides the approximate pre-construction and post-construction pavement areas, roadway basin areas, and required attenuation volumes for each of the basins.

Table 3-1: Drainage Sub-Basin Characteristics

Sub-Basin/ Segment Number	Sub-Basin Limits (Station)	Roadway Sub-Basin Area (Acres)	Pavement Area (Acres)		Attenuation Required (Acre-Feet)
			Pre- Const.	Post- Const.	
1	303+63.77 To 314+58.69	4.39	2.21	3.19	3.45
2	314+58.69 To 326+00.00	3.11	1.20	2.64	3.43
3	326+00.00 To 340+00.00	3.21	1.56	2.82	3.47
4	340+00.00 To 371+00.00	9.83	4.38	8.48	5.50
5	371+00.00 To 380+88.00	4.80	2.04	3.85	1.02
6	380+88.00 To 414+21.60	9.84	2.59	6.09	2.52
7	414+21.60 To 436+70.90	6.84	1.69	3.99	1.31
8	436+70.90 To 466+22.27	10.22	3.25	5.97	2.02
9	466+22.27 To 502+51.33	11.33	2.90	6.47	2.69

The following descriptions are provided for the conceptual drainage design within each basin:

Sub-basin No. 1 originates at the beginning of the Study limits (west of Highview Road) and terminates east of Lake Drive, approximately 0.207 miles (0.344 kilometers). Sub-basin No. 2 begins east of Lake Drive and terminates east of Oak Street South. Sub-basin No. 3 extends from east of Oak Street to west of Parsons Avenue. These sub-basins are considered to be within closed drainage basins. Due to the commercial development in the area, the application of long linear ponds is not practical. Therefore, partial or whole parcel takes within the vicinity of S.R. 574 will be required to provide storm water ponds that will accommodate the additional runoff volumes.

Sub-basin No. 4 begins west of Parsons Avenue and terminates west of Kingsway Road. This basin consists of french drains and is split by the high point at Parsons Avenue. West of Parsons Avenue the french drain is self-contained and does not have an outfall, whereas east of Parsons Avenue the french drain has a built-in relief pipe that outfalls eastward. Sub-basin No. 5 extends from west of Kingsway Road to east of Oak Street. Sub-basin No. 6 originates east of Oak Street and terminates west of Chastain Road. Sub-basin No. 7 begins west of Chastain Road and ends west of Valrico Road. Sub-basin No. 8 extends from west of Valrico Road to west of McIntosh Road. Sub-basin No. 9 originates west of McIntosh Road and terminates at the end of the Study limits, east of McIntosh Road. Sub-basins 4 through 9 are considered to be within open drainage basins; however, sub-basin 9 requires compensation for lost ditch volume (all other existing roadside ditches along the project provide more conveyance than attenuation and thus do not require compensation).

Refer to the Appendices in this report for the conceptual drainage design calculations and the alternative pond sites for these segments, which are summarized in Table 3-2 (aerial exhibits are also provided in the appendix for the alternative pond sites).

Table 3-2: Summary of Proposed Pond Site Characteristics

Pond Site	Segment No.	Required Top of Pond Area (Acres)	Storage Volume Provided (Acre-Ft.)	Treatment Volume Provided (Acre-Ft.)	Right-of-way Acquisition Required Acres
1A	1, 2, 3 & 4*	3.18	14.25	0.88	2.20
1B	1, 2, 3 & 4*	3.18	14.25	0.88	2.20
2A	4** & 5	0.80	2.82	0.87	1.34
2B	4** & 5	0.96	3.14	0.87	1.48
3A	6 & 7	1.23	5.99	0.84	2.19
3B	6 & 7	1.14	3.86	0.84	1.68
4A	8	0.95	2.30	0.50	1.53
4B	8	1.02	2.37	0.50	1.58
5A	9	1.34	6.96	0.54	2.05
5B	9	1.34	6.93	0.54	2.03

*Portion of sub-basin 4 that is west of Parsons Avenue

**Portion of sub-basin 4 that is east of Parsons Avenue

The sites shown for segments 1, 2, 3 and a portion of 4 includes a FDOT owned parcel that is close to S.R 574 and is well located at the lowest point of the segment with an adjacent outfall source. A second site was preliminarily evaluated that was located on Taylor Road north of S.R 574, but was dropped due to low hydraulic benefits. It should be noted that a portion of the existing roadway contains french drains that properly function and have not required the high level of maintenance that has been experienced in other areas of the District. It is therefore recommended that a portion of the new roadway contain french drains as part of the storm sewer system to augment the pond's storm water attenuation and treatment capabilities. Though the proposed pond was conservatively sized to exclude the benefits of a french drain system, this approach should be revisited in the future design phase.

Two alternative sites (2A and 2B) were identified for the portion of the corridor from Parsons Avenue to east of Kingsway Road (Oak Street). Site 2A is a commercial property (Car Wash) that is located in a wedged shaped parcel west of Kingsway Road between S.R. 574 and the CSX Railroad. This site contains a small pond with concrete block walls, and the proposed pond would require total acquisition of the site and demolition of the car wash and existing pond structure. This site is in a natural low area, is immediately adjacent to S.R 574, and can easily outfall eastward in the existing railroad ditch. A retaining wall would need to be constructed along the south side of the pond to obtain sufficient attenuation volume. The second alternative site is located on the east side of Kingsway Road approximately 1000 feet north of S.R. 574, on currently vacant land in front of a church and across the street from a historic property (the Old Seffener

Schoolhouse). This site does not have a natural outfall; therefore, a diversion structure would need to be applied within the S.R. 574 storm sewer system. Both sites are expected to function as dry ponds for stormwater treatment.

Two alternative sites (3A and 3B) were identified for the portion of the corridor from east of Kingsway Road (Oak Street) to west of Valrico Road. Both of these sites are located in close proximity to Lake Weeks, which is the ultimate outfall for this portion of the corridor and contains the lowest land. Both sites are located in currently vacant land within a low density residential area, avoid impacting the park and proposed residential sub-division at the lake, and can be easily reached by storm sewer from S.R. 574. These sites also provide compensation for a portion of the roadway between Lake Weeks Creek and Baker Canal that discharges directly to the canal, and are expected to function as extended wet detention ponds for stormwater treatment.

Two alternative sites (4A and 4B) were identified for the portion of the corridor from west of Valrico Road to west of McIntosh Road. Site 4A is located in a low area that was determined to be jurisdictional late in the Study. However, the wetlands are disturbed and marginal in quality, and consideration is expected from the permitting agencies for wetland improvement by constructing an extended wet detention pond. Site 4B is located in an upland area immediately east of Site 4A, which is currently being rezoned for a residential sub-division. Both sites are located on the opposite side of the CSX tracks from S.R. 574; therefore, culvert crossings beneath the tracks and maintenance access along the railroad right-of-way from Valrico Road will be required.

Two alternative sites (5A and 5B) were identified for the portion of the corridor from west of McIntosh Road to east of McIntosh Road. Both sites include compensation for lost ditch volume, since the large existing ditch between S.R. 574 and the CSX railroad provides significant attenuation (4.20 acre-feet) before outfalling towards Baker Canal. The sites will also require retaining walls along the north and west sides of the ponds to provide sufficient volume, and are expected to function as wet detention ponds for stormwater treatment.

Evaluation of Alternative Pond Sites

The existing and proposed land use data and planned developments were reviewed as part of the selection of the alternative pond sites. All proposed sites are located on currently vacant land except for the commercial properties at Pond Sites 2A and 5B, which would be significantly impacted by the recommended roadway improvements alone, and the residential properties at Pond Sites 5A and 5B. The sites have also been located in low areas convenient to the corridor for hydraulic purposes to avoid significantly increasing the roadway profile, pumping, or causing large areas of the corridor to have direct discharges and compensation requirements. Compensation for direct discharge should only be required for the short length of the corridor between Lake Weeks Creek and Baker Canal, as mentioned in section 3.1, and the only site that contains wetlands is Pond Site 4A, which are disturbed and marginal in quality. As mentioned in section 3.1, it is anticipated that the permitting agencies will consider Pond 4A as an improvement to this wetland by applying extended wet

detention and containing desirable plant species. However, mitigation costs under Senate Bill 1986 should be applied when comparing this site to its alternatives.

Since most of the alternative sites are in low development areas no significant utilities were observed except for Pond Sites 2A and 5B, which are commercial properties. Removal of existing utilities (including power, water and sanitary) will thus need to be included in the demolition of these sites, if they are acquired.

It should be noted that floodplain compensation is not required for the ponds since the only floodplain impacts are the culvert and bridge replacements at Lake Weeks Creek and Baker Canal, respectively. Since these impacts are to floodplain conveyance and not storage, the only compensation or mitigation that is required is to provide hydraulically equivalent structures (refer to the Study's separate LHR and Preliminary Bridge Analysis for additional information). The soils within the alternative pond sites are the same as those along the roadway, and consist of fine sands that either drain well (Lake and Candler soil types, pond sites 1A, 1B, 2A and 2B) or drain moderately to poorly (Seffner soil type, pond sites 3A, 3B, 4A, 4B, 5A and 5B). It should be noted that a poorly drained soil does not eliminate a pond site, but rather changes the storm water treatment method to extended wet detention. If a better soil type is available within a specific basin, then the advantages for a pond site would be greater pond depth and easier maintenance. However, this is not applicable to this Study's area.

The alternative sites were evaluated for archaeological and historical resources, potential contamination, and protected species and were included in the Study's separate environmental documents. None of these evaluations discovered resources that would exclude the use of these sites for ponds, nor require mitigation or special permitting for the above items.

Right-of-way costs and construction costs were obtained (refer to the appendices of this report) and are summarized in the table below.

Table 3-3: Right-of-way and Construction Costs for Proposed Pond Locations

Pond Site Number	Pond Right-of-way Cost	Pond Construction Cost
1A	\$2,129,300.00	\$180,400.00
1B	\$1,648,100.00	\$237,000.00
2A	\$0.00*	\$317,100.00
2B	\$1,020,500.00	\$252,200.00
3A	\$1,397,500.00	\$104,800.00
3B	\$843,300.00	\$69,900.00
4A	\$261,300.00	\$56,300.00
4B	\$428,800.00	\$61,500.00
5A	\$1,479,700.00	\$504,300.00
5B	\$1,023,100.00	\$646,100.00

*Affected properties were damaged out as part of the mainline right-of-way acquisitions

PERMIT REQUIREMENTS

Since there are no navigable waterways within the corridor, a United States Coast Guard permit is not required. Permitting will thus be met by a joint application for an Environmental Resource Permit to SWFWMD and USACOE. Wetland impacts will occur mostly in upland ditches; therefore, mitigation should only be considered for the impacts at Lake Weeks Creek and Baker Canal. These impacts are small and the existing wetlands are disturbed, do not provide wildlife habitat, and contain nuisance species, thus exemption from wetland mitigation should be pursued. An exception would be Pond Site 4A, as discussed in Sections 3.1 and 3.2 of this report.

A dredge and fill permit application may need to be processed with USACOE for the filling of the existing roadside ditches, but this is expected to meet Nationwide Permit requirements.

5.0 RECOMMENDATIONS

Segments 1, 2, 3 and a portion of 4 (from west of Highview Road to Parsons Avenue) – the recommended pond site is Pond Site 1B, which includes property owned by the FDOT, is located in a low area for this portion of the Study corridor, is not expected to have high groundwater constraints, and is adjacent to an available outfall. This site is recommended over Pond Site 1A due to lower anticipated right-of-way costs (all other features are nearly the same between the two sites).

Portions of segment 4 and segment 5 (from Parsons Avenue to east of Kingsway Road (Oak Street) – the recommended pond site is Pond Site 2A due to significantly lower right-of-way costs and simpler hydraulics (would not require constructing 1000 feet of stormsewer along Kingsway Avenue with a diversion structure, as would be needed for Pond Site 2B).


Segments 6 and 7 (from east of Kingsway Road (Oak Street) to west of Valrico Road) – Pond Sites 3A and 3B are similar in characteristics, benefits, and costs; however, Pond Site 3B is preferred due to a lower combined right-of-way and construction cost and less impacts to an adjacent commercial property.

Segment 8 (from west of Valrico Road to west of McIntosh Road) – Pond Site 4A is recommended due to a lower combined right-of-way and construction cost. It should be noted that if mitigation through Senate Bill 1986 is required, then approximately \$150,000 (depending on the year that the mitigation is applied) in additional costs will occur for Pond Site 4A. However, this site will still be the least expensive of the two alternatives.

Segment 9 (from west of McIntosh Road to east of McIntosh Road) – Pond Site 5B is recommended due to lower right-of-way costs, which more than offset the higher construction cost. These two sites slightly overlap and are very similar in most other features.

II. Basin Design

A. Segment Number 1



Begin Sta. 303+63.77 - Established based on the beginning of the 5-Lane Alternative Alignment

End Sta. 314+58.69 - End of the Curb and Gutter Section (SPN 10340-3503)

Construction

2a. Total (ROW) = $191,308.51 \text{ ft}^2 \approx 4.39 \text{ acres}$ (Measured in CADD)


$$\begin{aligned} \text{Pervious Area} = & [(303+95.72 - 303+63.77)(58.5)] + \left[\frac{1}{2}(44)(305+82.44 - \right. \\ & \left. 303+95.72) \right] + [(313+50 - 303+95.72)(52)] + \\ & \left[\frac{1}{2}(14)(313+50 - 307+60) \right] + [(314+58.69 - \\ & 313+50)(36)] + [(24)(785) + (24)(38)] + \\ & [(24)(32)] + [(314+58.69 - 303+95.72)(2)(2)] + \\ & [(305+90 - 303+63.77)(6) + (307+20 - \\ & 303+63.77)(6) + (314+58.69 - 307+36.64) \\ & (6)] \end{aligned}$$

Pervious Area = $96,241.26 \text{ ft}^2 \approx 2.21 \text{ acres}$ (Calc. based on Construction Plans, SPN 10340-3503)

67.00	Remarks	Prepared by SLW	Date 2/20/01
SR 574 (MILK BLVD.) PD3E Study		Checked by R/L	Date -

Basin Design

H. Segment Number 8



Pre-Construction

$$\text{Area Total (ROW)} = 445,099.30 \text{ ft}^2 = 10.22 \text{ acres}$$

$$\begin{aligned} \text{Impervious Area} &= \left[(447+70 - 436+70.90)(32) \right] + \left[(452+70 - \right. \\ &\quad \left. 447+70) \left(\frac{32+40.16}{2} \right) \right] + \left[(453+20 - \right. \\ &\quad \left. 452+70) \left(\frac{44+56}{2} \right) \right] + \left[(457+16 - 453+20)(56) \right] \\ &\quad + \left[(464+00 - 457+16) \left(\frac{50.01+39.6}{2} \right) \right] + \\ &\quad \left[(466+22.27 - 464+00) \left(\frac{35.5+39.6}{2} \right) \right] + \\ &\quad \left[(24)(68) + (36)(624) \right] \\ &= 141,359.66 \text{ ft}^2 \approx 3.25 \text{ acres} \end{aligned}$$

Post Construction

$$\text{Area Total (ROW)} = 445,099.30 \text{ ft}^2 = 10.22 \text{ acres}$$

$$\text{Impervious Area} = 259913.72 \text{ ft}^2 \approx 5.97 \text{ acres}$$

00	Remarks	Prepared by SLW	Date 3/21/01
R 574 (MLK Blvd.) PD3E Study		Checked by DPA	Date 4-1-02

LANDS 4A & 4B, 25-YR/24-HR STORM EVENT, $P_{25} = 8.2"$

LAND USE	CN	S	Q
RV	39	15.6	1.2
P	98	0.2	8.0
ND	100	0.0	8.2

PRE-CONSTRUCTION:

SEGMENT	AREA (AC)			RUN-OFF (IN)			TOTAL VOL (AC-FT)
	PERV	IMPERV	POND	PERV	IMPERV	POND	
8	6.97	3.25	0.00	1.2	8.0	8.2	2.86
TOTAL							2.86

POST-CONSTRUCTION:

SEGMENT	AREA (AC)			RUN-OFF (IN)			TOTAL VOL (AC-FT)
	PERV	IMPERV	POND	PERV	IMPERV	POND	
8	4.25	5.97	0.69	1.2	8.0	8.2	4.88
TOTAL		5.97					4.88

NOTE: POND AREA IS THE SURFACE AREA AT SHW (ELEV. 42.2).

REQUIRED TREATMENT VOL = $1" \times 5.97 \text{ Ac} = 0.50 \text{ AC-FT}$

REQUIRED ATTENUATION = $(4.88 - 2.86) = 2.02 \text{ AC-FT}$

WETLANDS PROVIDED

WETLANDS IMMEDIATELY EAST OF BAKER CANAL (WETLAND):

LAND ID 4A	EL (FT)	AREA (AC)	VOL (AC-FT)
P_{25}	45.0	0.95	2.30
TREATMENT	43.7	0.83	1.14
	42.2	0.69	0

WETLANDS FURTHER EAST OF BAKER CANAL (UPLAND):

LAND ID 4B	EL (FT)	AREA (AC)	VOL (AC-FT)
P_{25}	45.0	1.02	2.37
TREATMENT	43.7	0.86	1.15
	42.2	0.67	0

2000-01-01 to 2000-01-31

DATE	TIME	LOCATION	STATUS
2000-01-01	08:00	101	OK
2000-01-01	09:00	101	OK
2000-01-01	10:00	101	OK
2000-01-01	11:00	101	OK
2000-01-01	12:00	101	OK
2000-01-01	13:00	101	OK
2000-01-01	14:00	101	OK
2000-01-01	15:00	101	OK
2000-01-01	16:00	101	OK
2000-01-01	17:00	101	OK
2000-01-01	18:00	101	OK
2000-01-01	19:00	101	OK
2000-01-01	20:00	101	OK
2000-01-01	21:00	101	OK
2000-01-01	22:00	101	OK
2000-01-01	23:00	101	OK

DATE	TIME	LOCATION	STATUS
2000-01-02	08:00	101	OK
2000-01-02	09:00	101	OK
2000-01-02	10:00	101	OK
2000-01-02	11:00	101	OK
2000-01-02	12:00	101	OK
2000-01-02	13:00	101	OK
2000-01-02	14:00	101	OK
2000-01-02	15:00	101	OK
2000-01-02	16:00	101	OK
2000-01-02	17:00	101	OK
2000-01-02	18:00	101	OK
2000-01-02	19:00	101	OK
2000-01-02	20:00	101	OK
2000-01-02	21:00	101	OK
2000-01-02	22:00	101	OK
2000-01-02	23:00	101	OK

DATE	TIME	LOCATION	STATUS
2000-01-03	08:00	101	OK
2000-01-03	09:00	101	OK
2000-01-03	10:00	101	OK
2000-01-03	11:00	101	OK
2000-01-03	12:00	101	OK
2000-01-03	13:00	101	OK
2000-01-03	14:00	101	OK
2000-01-03	15:00	101	OK
2000-01-03	16:00	101	OK
2000-01-03	17:00	101	OK
2000-01-03	18:00	101	OK
2000-01-03	19:00	101	OK
2000-01-03	20:00	101	OK
2000-01-03	21:00	101	OK
2000-01-03	22:00	101	OK
2000-01-03	23:00	101	OK

2000-01-04 to 2000-01-31

2000-01-04 to 2000-01-31

2000-01-04 to 2000-01-31

2000-01-04 to 2000-01-31

2000-01-04 to 2000-01-31

2000-01-04 to 2000-01-31

2000-01-04 to 2000-01-31

2000-01-04 to 2000-01-31

2000-01-04 to 2000-01-31

2000-01-04 to 2000-01-31

2000-01-04 to 2000-01-31

2000-01-04 to 2000-01-31

2000-01-04 to 2000-01-31

2000-01-04 to 2000-01-31

ONDS 5A & 5B, 25-YR/24-HR STORM EVENT, $P_{25} = 8.2"$

LAND USE	CN	S	Q
PERV	39	15.6	1.2
P	98	0.2	8.0
POND	100	0.0	8.2

PRE-CONSTRUCTION:

SEGMENT	AREA (AC)			RUN-OFF (IN)			TOTAL VOL (AC-FT)
	PERV	IMPERV	POND	PERV	IMPERV	POND	
9	8.43	2.90	0.00	1.2	8.0	8.2	2.78
TOTAL							2.78

POST-CONSTRUCTION:

SEGMENT	AREA (AC)			RUN-OFF (IN)			TOTAL VOL (AC-FT)
	PERV	IMPERV	POND	PERV	IMPERV	POND	
9	4.86	6.47	0.98	1.2	8.0	8.2	5.47
TOTAL		6.47					5.47

NOTE: POND AREA IS THE SURFACE AREA AT SHW (ELEV. ⁵²~~42.2~~). IN OTHER PORTIONS OF THE PROJECT THE EXISTING ROADSIDE DITCHES PROVIDE CONVEYANCE, WHICH WILL BE MAINTAINED BY THE BUILD ALTERNATIVE'S DRNG FEATURES. HOWEVER, THIS PORTION OF THE PROJECT SHOULD ALSO COMPENSATE FOR THE LOST STORAGE OF THE DITCHES (THE 25-YR, 24-HR CRITERIA IS STILL APPLICABLE).

REQUIRED TREATMENT VOL = $1" \times 6.47 \text{ Ac} = 0.54 \text{ AC-FT}$

REQUIRED ATTENUATION = $(5.47 - 2.78) = 2.69 \text{ AC-FT}$

PLUS EXISTING DITCH VOL. (SEE NOTE ABOVE) 4.20

TOTAL ATTENUATION 6.89 AC-FT

ATTENUATION'S PROVIDED

ATTENUATION IMMEDIATELY WEST OF McINTOSH RD (RESIDENTIAL PROPERTIES, RETAINING WALLS ON WEST & NORTH SIDES):

D 5A	EL (FT)	AREA (AC)	VOL (AC-FT)
I_{25}	58.0	1.34	6.96
TREATMENT	53.5	1.07	1.54
	52.0	0.98	0

ATTENUATION IMMEDIATELY WEST OF McINTOSH RD (INCLUDES COMMERCIAL PROP'Y, RETAINING WALL ON NORTH SIDE):

D 5B	EL (FT)	AREA (AC)	VOL (AC-FT)
I_{25}	58.0	1.34	6.93
TREATMENT	53.5	1.06	1.52
	52.0	0.97	0

ND SITES 1A & 1B

CAVATION (BASING CALL. ON TOTAL POND STORAGE
MPENSATES FOR BERTH CONST) = $14.25 \text{ AC-FT} \times 93510 \frac{\text{S.F.}}{\text{AC}} \times$
 $\frac{1 \text{ C.Y.}}{27 \text{ C.F.}} = \underline{22,990 \text{ C.Y.}}$

EARING & GRUBBING = $\underline{4.09 \text{ AC.}}$

D = $(4.09 \text{ AC} - 3.18 \text{ AC}) \times 4080 \frac{\text{SY}}{\text{AC}} = \underline{9,404 \text{ S.Y.}}$

FENCE = $\underline{1,764'}$ (4 COR POSTS, 2 END POSTS, 1 PULL POST,
1 GATE).

DD'L STORMSEWER FOR SITE 1B = $\underline{307'}$ (54"Ø PLUS (1) TYPE
J MH).

COMMON CONST COSTS :

C & G	$4.09 \text{ AC} \times \$5,200/\text{AC} =$	$\underline{\$21,300}$
EXC	$22,990 \text{ CY} \times \$3.00/\text{CY} =$	$\underline{69,000}$
SOD	$9,404 \text{ SY} \times \$1.50/\text{SY} =$	$\underline{6,600}$
FENCE	$1,764' \times \$8.00/\text{FT} =$	$\underline{14,100}$
	TOTAL	$\underline{\$111,000}$

SITE 1B:

54"Ø	$307 \text{ LF} \times \$100/\text{LF} =$	$\underline{\$30,700}$
J-7 MH		$\underline{9,100}$
		$\underline{\$34,800}$

SITE 1A -	$\underline{\$111,000}$
25% CONTING.	$\underline{27,800}$
	$\underline{138,800}$
30% DES & CEE	$\underline{41,600}$
	$\underline{\underline{\$180,400}}$

INT.)

00367.00	Remarks	Prepared by MLK	Date 5-22-02
	MLK PDEE	Checked by SLW	Date 5/23/02
	Pond Const Costs		Sheet 1 of 1

MEMORANDUM FOR THE RECORD

DATE: 10/1/78
TO: Mr. [Name]
FROM: Mr. [Name]
SUBJECT: [Subject]

1. [Text]
2. [Text]
3. [Text]
4. [Text]
5. [Text]

6. [Text]
7. [Text]
8. [Text]
9. [Text]
10. [Text]

11. [Text]
12. [Text]
13. [Text]
14. [Text]
15. [Text]

POND SITES 1A & 1B CONT.)

SITE 1B -	\$111,000
ADD'L S.S. & STRUCT.	<u>34,800</u>
	145,800
25% CONTING	<u>36,500</u>
	182,300
30% DES & CEE	<u>54,700</u>
	<u><u>\$237,000</u></u>

POND SITES 2A & 2B

SITE 2A -	CLEARING & GRUBBING = <u>1.34 Ac.</u>
EXC	$2.82 \text{ Ac} - 44 \times 43560 \frac{\text{SF}}{\text{AC}} \times \frac{1 \text{ CY}}{27 \text{ CF}} = \underline{4,550 \text{ CY.}}$
SOD	$(1.34 \text{ Ac} - 0.61 \text{ Ac}) \times 4840 \frac{\text{SY}}{\text{Ac}} = \underline{3,533 \text{ SY.}}$
FENCE	<u>1,393'.</u>
CONC. SHUT PILE WALL	$-(12' \times 438') = \underline{5,256 \text{ SF}}$
C & G	$1.34 \text{ Ac} \times \$5,200/\text{Ac} = \$7,000$
EXC	$4,550 \text{ CY} \times \$3.00/\text{CY} = 13,700$
SOD	$3,533 \text{ SY} \times \$1.50/\text{SY} = 5,300$
FENCE	$1,393 \text{ LF} \times \$8.00/\text{LF} = 11,100$
SHUT PILE	$5,256 \text{ SF} \times \$30/\text{SF} = \underline{158,000}$
	\$195,100
25% CONTING	<u>48,800</u>
	243,900
30% DES & CEE	<u>73,200</u>
	<u><u>\$317,100</u></u>

(CONT.)

300362.00	Remarks	Prepared by <u>DAK</u>	Date <u>5-22-02</u>
	<u>MLK PD & E</u>	Checked by <u>SLW</u>	Date <u>5/23/02</u>

ND SITES 2A & 2B (CONT.)

SITE 2B -

$$C \& G = 1.48 \text{ Ac.}$$

$$EXC = 3.14 \text{ Ac.} \cdot 4 \times \frac{43560 \text{ SF}}{\text{Ac}} \times \frac{1 \text{ CY}}{27 \text{ CF}} = \underline{5,066 \text{ CY.}}$$

$$SOD = (1.48 \text{ Ac.} - 0.61 \text{ Ac.}) \times \frac{9,840 \text{ SY}}{\text{Ac}} = \underline{9,211 \text{ SY.}}$$

$$\text{FENCE} = \underline{1,200'}$$

ADD'L PIPE = 1,000' (60" ϕ PLUS (4) TYPE
J MH'S)

$$C \& G \quad 1.48 \text{ Ac.} \times \$5,200/\text{Ac} = \$7,700$$

$$EXC \quad 5,066 \text{ CY} \times \$3.00/\text{CY} = 15,200$$

$$SOD \quad 9,211 \text{ SY} \times \$1.50/\text{SY} = 6,300$$

$$\text{FENCE} \quad 1,200 \text{ LF} \times \$8/\text{LF} = 9,600$$

$$60" \phi \quad 1,000 \text{ LF} \times \$100/\text{LF} = 100,000$$

$$\text{J-7 MH} \quad 4 \times \$4,100/\text{EA} = \underline{16,400}$$

$$\underline{\$155,200}$$

$$25\% \text{ CONTING} \quad \underline{38,800}$$

$$194,000$$

$$30\% \text{ DES \& CFI} \quad \underline{58,200}$$

$$\underline{\underline{\$252,200}}$$

ND SITES 3A & 3B

SITE 3A -

$$C \& G = 2.19 \text{ Ac.}$$

$$EXC = 5.99 \text{ Ac.} \cdot 4 \times \frac{43560 \text{ SF}}{\text{Ac}} \times \frac{1 \text{ CY}}{27 \text{ CF}} = \underline{9,669 \text{ CY}}$$

$$SOD = (2.19 \text{ Ac.} - 0.64 \text{ Ac.}) \times \frac{9,840 \text{ SY}}{\text{Ac}} = \underline{7,502 \text{ SY}}$$

$$\text{FENCE} = \underline{1,609'}$$

(T.)

367.00	Remarks	Prepared by DAK	Date 5-22-02
MLK PDIE		Checked by SLW	Date 5-22-02

**FLORIDA DEPARTMENT OF TRANSPORTATION
DISTRICT SEVEN RIGHT OF WAY COST ESTIMATE**

HDR#: 06884-888-088-24

FMA: 255893 1	Former WPIA: N/A	District: Seven
County: Hillsborough	FAP No.: 2081-018P	Date: 20-Dec-01
State Rd.: 574	Alternate: Pond 2B	C.E. Sequence: N/A
Project Des.: SR 574 PD&E Study from CR 579 to McIntosh Rd		

Parcels	Gross	Net	Estimated Relocates:
Commercial	0	0	Business
Residential	1	1	Residential
Unimproved	1	1	Signs
			Special
Total Parcels	2	2	Total Relocates

RW SUPPORT COSTS (PHASE 41)				Amount
1. Direct Labor Cost	(Parcels)	2	x	6,500 =
2. Indirect Overhead	(Parcels)	2	x	0 =
3.				
TOTAL PHASE 41				\$13,000

RW OPS (PHASE 42)				Amount
4. Appraisal Fees Through Trial	2	Parcels	x	12,000 =
5. Business Damage CPA Fees Through Trial	0	Claims	x	19,000 =
6. Court Reporter & Process Servers	75%	x	2 =	1,000
7. Expert Witness	75%	x	2 =	60,000
8. Mediators	50%	x	2 =	2,400
9. Demolition, Asb. Abate., Survey, etc..	1	Imprvmet	x	15,000 =
10. Miscellaneous Contracts	1	Per Project	x	15,000 =
11. Appraisal Fee Review	1	Parcels	x	5,000 =
12.				
TOTAL PHASE 42				\$122,400

RW LAND COSTS (PHASE 43)				Amount	Subtotal
13. Land, Improvements & Severance Damages and Cost to Cure Amount	0	x	130% * Design plan stage	=	0
14. Water Retention & Mit.	351,795	x	130% (0 Parcels w/o R/W Acq)	=	457,334
15. SUBTOTAL			(Lines 13 & 14)		457,334
16. Admin. Settlements (Factor)	45%	x	30% of Line 15)	=	61,700
17. Litigation Awards (Factor)	60%	x	70% of Line 15)	=	192,180
18. Business Damages (Claims)	0	x	\$0)	=	0
19. Bus. Damages Incrs. (Factor)	25%	x	\$)	=	0
20. Owner Appr. Fees (Parcels)	2	x	\$10,000)	=	20,000
21. Owner CPA Fees (Claims)	0	x	\$10,000)	=	0
22. Defend Atty Fees (Sum of Lines 16, 17 & 18)	253,800	x	40%)	=	101,560
23. Owner Expert Witness (Comm. + Unimp.)	0	x	1) x 10,000	=	10,000
24. Other Condem. Costs	2	x	\$500	=	1,000
25. SUBTOTAL			(Lines 16 thru 24)	=	394,300
26.					
TOTAL PHASE 43					\$851,600

* Design contingency for design plan stage:
(1) PD&E plans - 130% (2) 30% plans - 125% (3) 60% plans - 120% (4) 90% plans - 115% (5) 268 Date - 110%

27. Acquisition Consultant-50% of parcels	\$20,000	x	1	TOTAL PHASE 42	\$20,000
---	----------	---	---	----------------	----------

RELOCATION COSTS (PHASE 45)				Number	Amount
28. Owner Replacement Housing	\$20,000	x	0	=	0
29. Tenant	\$10,000	x	1	=	10,000
30. Residential Move Costs	\$1,500	x	1	=	1,500
31. Business/Farm	\$20,000	x	0	=	0
32. Personal Property	\$2,000	x	1	=	\$2,000
33. (Lines 28 thru 32)					
34. Relocation Services Cost	\$1,350			(Not in Phase Total)	
35.					
36.					
37. (All Phases)					
TOTAL PHASE 45					\$13,500

37. (All Phases)	TOTAL ESTIMATE	\$1,020,500
------------------	----------------	-------------

Appraisal:	Daniel Trosper	Signed:	<i>Daniel Trosper</i>	Date:	5/15/02
Bus. Dam.:	N/A	Signed:		Date:	
Relocation:	Daniel Trosper	Signed:		Date:	
Overall Review:	Marilyn Jackson	Signed:	<i>Marilyn Jackson</i>	Date:	5/15/02

Cost Estimate Sequence #: Dated: In the Amount of \$ Data Input Completion Date:

REMARKS: Parcel 2B-1 is owned by and appears to be a parsonage for the First United Methodist Church of Selfner, located directly to the south.

The following indicates the estimator's confidence in the above estimate:	Future Value Factors @	10%
Type A - Indicates the most confidence	Year One	1.1000
Type B - Indicates above average confidence	Year Two	1.2100
X Type C - Indicates below average confidence	Year Three	1.3310
Type D - Indicates the least or no confidence	Year Four	1.4641
	Year Five	1.6105

The following indicates the Department's purpose for this estimate:

Work Program Update: _____ Special Purpose: ☒ Docs to RW: _____

Comments: _____

Date		Description		Amount	
1900	Jan 1	Balance		100.00	
1900	Jan 15	Interest		1.00	
1900	Feb 1	Interest		1.00	
1900	Feb 15	Interest		1.00	
1900	Mar 1	Interest		1.00	
1900	Mar 15	Interest		1.00	
1900	Apr 1	Interest		1.00	
1900	Apr 15	Interest		1.00	
1900	May 1	Interest		1.00	
1900	May 15	Interest		1.00	
1900	Jun 1	Interest		1.00	
1900	Jun 15	Interest		1.00	
1900	Jul 1	Interest		1.00	
1900	Jul 15	Interest		1.00	
1900	Aug 1	Interest		1.00	
1900	Aug 15	Interest		1.00	
1900	Sep 1	Interest		1.00	
1900	Sep 15	Interest		1.00	
1900	Oct 1	Interest		1.00	
1900	Oct 15	Interest		1.00	
1900	Nov 1	Interest		1.00	
1900	Nov 15	Interest		1.00	
1900	Dec 1	Interest		1.00	
1900	Dec 15	Interest		1.00	
1900	Dec 31	Interest		1.00	
1901	Jan 1	Balance		100.00	
1901	Jan 15	Interest		1.00	
1901	Feb 1	Interest		1.00	
1901	Feb 15	Interest		1.00	
1901	Mar 1	Interest		1.00	
1901	Mar 15	Interest		1.00	
1901	Apr 1	Interest		1.00	
1901	Apr 15	Interest		1.00	
1901	May 1	Interest		1.00	
1901	May 15	Interest		1.00	
1901	Jun 1	Interest		1.00	
1901	Jun 15	Interest		1.00	
1901	Jul 1	Interest		1.00	
1901	Jul 15	Interest		1.00	
1901	Aug 1	Interest		1.00	
1901	Aug 15	Interest		1.00	
1901	Sep 1	Interest		1.00	
1901	Sep 15	Interest		1.00	
1901	Oct 1	Interest		1.00	
1901	Oct 15	Interest		1.00	
1901	Nov 1	Interest		1.00	
1901	Nov 15	Interest		1.00	
1901	Dec 1	Interest		1.00	
1901	Dec 15	Interest		1.00	
1901	Dec 31	Interest		1.00	
1902	Jan 1	Balance		100.00	
1902	Jan 15	Interest		1.00	
1902	Feb 1	Interest		1.00	
1902	Feb 15	Interest		1.00	
1902	Mar 1	Interest		1.00	
1902	Mar 15	Interest		1.00	
1902	Apr 1	Interest		1.00	
1902	Apr 15	Interest		1.00	
1902	May 1	Interest		1.00	
1902	May 15	Interest		1.00	
1902	Jun 1	Interest		1.00	
1902	Jun 15	Interest		1.00	
1902	Jul 1	Interest		1.00	
1902	Jul 15	Interest		1.00	
1902	Aug 1	Interest		1.00	
1902	Aug 15	Interest		1.00	
1902	Sep 1	Interest		1.00	
1902	Sep 15	Interest		1.00	
1902	Oct 1	Interest		1.00	
1902	Oct 15	Interest		1.00	
1902	Nov 1	Interest		1.00	
1902	Nov 15	Interest		1.00	
1902	Dec 1	Interest		1.00	
1902	Dec 15	Interest		1.00	
1902	Dec 31	Interest		1.00	

**FLORIDA DEPARTMENT OF TRANSPORTATION
DISTRICT SEVEN RIGHT OF WAY COST ESTIMATE**

HDR#: 11573-025-C98-25

FME: 255893 1	Former WPI#: N/A	District: Seven
County: Hillsborough	FAP No.: 2081-018P	Date: 19-Jul-02
State Rd.: 574	Alternate: Pond 3A	C.E. Sequence: N/A
Project Des.: SR 574 PD&E Study from CR 579 to McIntosh Rd		

Parcels	Gross	Net	Estimated Relocates:
Commercial	1	0	Business
Residential	0	0	Residential
Unimproved	0	0	Signs
			Special
Total Parcels	1	0	Total Relocates

R/W SUPPORT COSTS (PHASE 41)

1. Direct Labor Cost	(Parcels	0	x	8,500 =	Rate)	Amount	0
2. Indirect Overhead	(Parcels	0	x	0 =	Rate)	Amount	0
3.						TOTAL PHASE 41	\$0

R/W OPS (PHASE 4B)

4. Appraisal Fee Through Trail	0	Parcels	x	12,000 =	Amount	0	
5. Business Damage CPA Fees Through Trail	1	Claims	x	19,000 =	Amount	19,000	
6. Court Reporter & Process Servers	75%	x	0 =	0	Parcels	x	
7. Expert Witness	75%	x	0 =	0	Parcels	x	
8. Mediators	50%	x	0 =	0	Parcels	x	
9. Demolition, Ass. Abate., Survey, etc.				1	Improvet	x	
10. Miscellaneous Contracts				1	Per Project	x	
11. Appraisal Fee Review				0	Parcels	x	
12.						TOTAL PHASE 4B	\$49,000

R/W LAND COSTS (PHASE 43)

13. Land, Improvements & Severance Damages and Cost to Cure Amount	0	x	130% * Design plan stage	=	0	Amount		Subtotal
14. Water Retention & Mit.	479,868	x	130% (0 Parcels w/ R/W Acq)	=	623,828			
15. SUBTOTAL							623,828	
16. Admin. Settlements (Factor	0%	x	0% of Line 15)	=	0			
17. Litigation Awards (Factor	60%	x	100% of Line 15)	=	374,300			
18. Business Damages (Claims	1	x	\$0	=	123,800			
19. Bus. Damages Incur(Factor	25%	x	\$ 123,800)	=	31,000			
20. Owner Appr. Fees (Parcels	0	x	\$10,000)	=	0			
21. Owner CPA Fees (Claims	1	x	\$10,000)	=	10,000			
22. Defend. Atty Fees (Sum of Lines 18, 17 & 19)	405,300	x	40%	=	162,100			
23. Owner Expert Wfne(Comm.+Unimp.)	0	x	0) 18,000	=	0			
24. Other Condemn. Costs	0	x	\$500	=	0			
25. SUBTOTAL							701,200	
26.						TOTAL PHASE 43	\$1,325,000	

* Design contingency for design plan stage:
(1) PD&E plans - 130% (2) 30% plans - 125% (3) 60% plans - 120% (4) 90% plans - 115% (5) 268 Date - 110%

R/W ACQUISITION CONSULTANT (PHASE 42)

27. Acquisition Consultant-50% of parcels	\$20,000	x	0	=	0	TOTAL PHASE 42	\$0
---	----------	---	---	---	---	-----------------------	-----

RELOCATION COSTS (PHASE 45)

Replacement Housing		Number	Amount
28. Owner	\$20,000	x	1 = 20,000
29. Tenant	\$10,000	x	0 = 0
Mova Costs			
30. Residential	\$1,500	x	1 = 1,500
31. Business/Farm	\$20,000	x	0 = 0
32. Personal Property	\$2,000	x	1 = 2,000
33. (Lines 28 thru 32)			TOTAL PHASE 45
34. Relocation Services Cost	\$2,350	(Not in Phase Total)	\$23,500

35.
36.
37. (All Phases) **TOTAL ESTIMATE** \$1,397,500

Appraisal: Daniel Trospen	Signed: Daniel Trospen	Date: 7/18/02
Bus. Dam. Gerson Preston Robinson	Signed: Gerson Preston Robinson	Date: 7/18/02
Relocation: Daniel Trospen	Signed: Daniel Trospen	Date: 7/18/02
Overall Review: Marilyn Jackson	Signed: Marilyn Jackson	Date: 7/18/02

Cost Estimate Sequence #: Dated: In the Amount of \$ Date Input Completion Date:

REMARKS: This parcel was counted in the mainline taking.
This pond site involves two properties, per County maps. The establishment of the parent tract is based on unity of use and related ownership. Vehicles related to the warehouse property appear to be parked on the residential property.

There is a discrepancy between County and FDOT maps on this site. County maps show the west lot line for the warehouse property shifted further west where there may not be an encroachment from any vehicles on the residential property.

The following indicates the estimator's confidence in the above estimate:	Future Value Factors @	10%
Type A - indicates the most confidence	Year One	1.1000
Type B - indicates above average confidence	Year Two	1.2100
X Type C - indicates below average confidence	Year Three	1.3310
Type D - indicates the least or no confidence	Year Four	1.4641
	Year Five	1.6105

The following indicates the Department's purpose for this estimate:
Work Program Update: Gaming 1: Special Purpose: Docs to RW: Comments:

**FLORIDA DEPARTMENT OF TRANSPORTATION
DISTRICT SEVEN RIGHT OF WAY COST ESTIMATE**

HDR#: 11573-025-096-25

FM#: 255893 1	Former WPI#: N/A	District: Seven
County: Hillsborough	FAP No.: 2081-018P	Date: 15-May-02
State Rd.: 574	Alternate: Pond 3B	C.E. Sequence: N/A
Project Des.: SR 574 PD&E Study from CR 579 to McIntosh Rd		

Parcels	Gross	Net	Estimated Relocates:
Commercial	0	0	Business
Residential	1	0	Residential
Unimproved	0	0	Signs
			Special
Total Parcels	1	0	Total Relocates

R/W SUPPORT COSTS (PHASE 41)				Amount	
1. Direct Labor Cost	(Parcels)	0	x	9,500 = Rate)	0
2. Indirect Overhead	(Parcels)	0	x	0 = Rate)	0
3.					
TOTAL PHASE 41					\$0

R/W OPS (PHASE 4B)				Amount	
4. Appraisal Fees Through Trial	0	Parcels	x	12,000 =	0
5. Business Damage CPA Fees Through Trail	0	Claims	x	19,000 =	0
6. Court Reporter & Process Servers	75%	0	Parcels	x	500 =
7. Expert Witness	75%	0	Parcels	x	30,000 =
8. Mediators	50%	0	Parcels	x	2,400 =
9. Demolition, Asb. Abate., Survey, etc.		0	Imprvmet	x	15,000 =
10. Miscellaneous Contracts		1	Per Project	x	15,000 =
11. Appraisal Fee Review		0	Parcels	x	5,000 =
12.					
TOTAL PHASE 4B					\$15,000

R/W LAND COSTS (PHASE 43)				Amount	Subtotal
13. Land, Improvements & Severance Damages and Cost to Cure Amount	0	x	130% * Design plan stage =	0	
14. Water Retention & Mit.	348,340	x	130% (0 Parcels w/o R/W Acq)	450,242	
15. SUBTOTAL			(Lines 13 & 14)		450,242
16. Admin. Settlements (Factor	0%	x	0% of Line 15)	=	0
17. Litigation Awards (Factor	50%	x	100% of Line 15)	=	270,100
18. Business Damages (Claims	0	x	\$0)	=	0
19. Bus. Damages Incrs (Factor	25%	x	\$ -)	=	0
20. Owner Appr. Fees (Parcels	0	x	\$10,000)	=	0
21. Owner CPA Fees (Claims	0	x	\$10,000)	=	0
22. Defend. Atty Fees (Sum of Lines 18, 17 & 19)	270,100	x	40%)	=	108,000
23. Owner Expert Witne (Comm.+Unimp.)	0	+	0) : 18,000	=	0
24. Other Condemn. Costs	0	x	\$500	=	0
25. SUBTOTAL			(Lines 16 thru 24)	=	378,100
26.					
TOTAL PHASE 43					\$828,300

Design contingency for design plan stage:
(1) PD&E plans - 130% (2) 30% plans - 125% (3) 60% plans - 120% (4) 90% plans - 115% (5) 268 Date - 110%

R/W ACQUISITION CONSULTANT (PHASE 42)				Amount	
27. Acquisition Consultant-50% of parcels	\$20,000	x	0		
TOTAL PHASE 42					\$0

RELOCATION COSTS (PHASE 45)				Amount	
Replacement Housing					
28. Owner	\$20,000	x	0	=	0
29. Tenant	\$10,000	x	0	=	0
Move Costs					
30. Residential	\$1,500	x	0	=	0
31. Business/Farm	\$20,000	x	0	=	0
32. Personal Property	\$2,000	x	0	=	\$0
33. (Lines 28 thru 32)					
TOTAL PHASE 45					\$0
34. Relocation Services Cost	\$0	(Not in Phase Total)			
35.					
36.					
37.					
(All Phases) TOTAL ESTIMATE					\$843,300

Appraisal:	Daniel Trosper	Signed:	<i>Daniel Trosper</i>	Date:	5/15/02
Bus. Dam.	N/A	Signed:		Date:	
Relocation:	N/A	Signed:		Date:	
Overall Review:	Marilyn Jackson	Signed:	<i>Marilyn Jackson</i>	Date:	5/15/02

Cost Estimate Sequence #:	Dated:	In the Amount of \$	Data Input Completion Date:
---------------------------	--------	---------------------	-----------------------------

REMARKS: This parcel was counted in the mainline taking.

The following indicates the estimator's confidence in the above estimate:		Future Value Factors @	10%
Type A - indicates the most confidence		Year One	1.1000
Type B - indicates above average confidence		Year Two	1.2100
X Type C - indicates below average confidence		Year Three	1.3310
Type D - indicates the least or no confidence		Year Four	1.4641
		Year Five	1.6105

The following indicates the Department's purpose for this estimate:			
Work Program Update:	Gaming 1:	Special Purpose:	X Docs to RW:
Comments:			

**FLORIDA DEPARTMENT OF TRANSPORTATION
DISTRICT SEVEN RIGHT OF WAY COST ESTIMATE**

HDR#: 11573-025-096-25

255893 1	Former WPI#:	N/A	District:	Seven
Hillsborough	FAP No.:	2081-018P	Date:	May 15, 2002
574	Alternate:	Pond 4A	C.E. Sequence	N/A
Des. SR 574 PD&E Study from CR 579 to McIntosh Rd				

Gross	Net	Estimated Relocates:
0	0	Business
1	1	Residential
0	0	Signs
0	0	Special
1	1	Total Relocates

SUPPORT COSTS (PHASE 41)				Amount
Direct Labor Cost	(Parcels)	1 x 8,500 =	Rate)	8,500
Direct Overhead	(Parcels)	1 x 0 =	Rate)	0
TOTAL PHASE 41				\$6,500

PS (PHASE 4B)				Amount
Appraisal Fees Through Trail	1	Parcels x	12,000 =	12,000
Business Damage CPA Fees Through Trail	0	Claims x	19,000 =	0
Expert Reporter & Process Servers	1	Parcels x	500 =	500
Expert Witness	1	Parcels x	30,000 =	30,000
Mediators	1	Parcels x	2,400 =	2,400
Demolition, Asb. Abate., Survey, etc.	0	Imprvmet x	15,000 =	0
Miscellaneous Contracts	1	Per Project x	15,000 =	15,000
Appraisal Fee Review	1	Parcels x	5,000 =	5,000
TOTAL PHASE 4B				\$64,900

AND CDSTS (PHASE 43)				Amount	Subtotal
Land, Improvements & Severance Damages	0	x	130% * Design plan stage =	0	
Land Cost to Cure Amount	86,847	x	130% (0 Parcels w/o R/W Acq)	86,841	
Water Retention & Mit.			(Lines 13 & 14)		86,841
TOTAL					
Admin. Settlements (Factor	0%	x	0% of Line 15)	=	0
Litigation Awards (Factor	60%	x	100% of Line 15)	=	52,000
Business Damages (Claims	0	x	\$0)	=	0
Business Damages Incr (Factor	25%	x	\$ -)	=	0
Owner Appr. Fees (Parcels	1	x	\$10,000)	=	10,000
Owner CPA Fees (Claims	0	x	\$10,000)	=	0
Defend. Atty Fees (Sum of Lines 16, 17 & 19)	52,000	x	40%)	=	20,800
Owner Expert Witne (Comm.+Unimp.)	0	+	0)	=	0
Other Condemn. Costs	1	x	\$500	=	500
TOTAL			(Lines 16 thru 24)	=	83,300
TOTAL PHASE 43					\$169,900

Design contingency for design plan stage:
 (1) PD&E plans - 130% (2) 30% plans - 125% (3) 60% plans - 120% (4) 90% plans - 115% (5) 258 Date - 110%

ACQUISITION CONSULTANT (PHASE 42)			
Acquisition Consultant-50% of parcels	\$20,000	x	1
TOTAL PHASE 42			\$20,000

REPLACEMENT COSTS (PHASE 45)			
Replacement Housing	Number	Amount	
Owner	\$20,000 x 0 =	0	
Owner	\$10,000 x 0 =	0	
Move Costs			
Residential	\$1,500 x 0 =	0	
Business/Farm	\$20,000 x 0 =	0	
Personal Property	\$2,000 x 0 =	\$0	
TOTAL PHASE 45			\$0
Relocation Services Cost \$0 (Not in Phase Total)			

(All Phases)	TOTAL ESTIMATE	\$261,300
--------------	-----------------------	------------------

Daniel Trosper	Signed:	<i>[Signature]</i>	Date:	5/15/02
N/A	Signed:		Date:	
N/A	Signed:		Date:	
View: Marilyn Jackson	Signed:	<i>[Signature]</i>	Date:	5/15/02

ate Sequence #:	Dated:	In the Amount of \$	Data Input Completion Date:
-----------------	--------	---------------------	-----------------------------

Administrative settlements and litigation awards have been changed to reflect one ownership. Administrative settlements are considered to be zero, while litigation is factored at 60% of land and improvement value.

Indicates the estimator's confidence in the above estimate:	Future Value Factors @	10%
Type A - Indicates the most confidence	Year One	1.1000
Type B - Indicates above average confidence	Year Two	1.2100
Type C - Indicates below average confidence	Year Three	1.3310
Type D - Indicates the least or no confidence	Year Four	1.4641
	Year Five	1.6105

Indicates the Department's purpose for this estimate:

Update: _____ Gaming I: _____ Special Purpose: ☒ Docs to RW: _____

UNITED STATES		DEPARTMENT OF THE ARMY		OFFICE OF THE CHIEF OF ENGINEERS		WASHINGTON, D. C.	
REPORT OF		COMMISSIONER OF THE DISTRICT OF COLUMBIA		OFFICE OF THE CHIEF OF ENGINEERS		WASHINGTON, D. C.	
TITLE		SUBJECT		DATE		BY	
1. TITLE		2. SUBJECT		3. DATE		4. BY	
5. TITLE		6. SUBJECT		7. DATE		8. BY	
9. TITLE		10. SUBJECT		11. DATE		12. BY	
13. TITLE		14. SUBJECT		15. DATE		16. BY	
17. TITLE		18. SUBJECT		19. DATE		20. BY	
21. TITLE		22. SUBJECT		23. DATE		24. BY	
25. TITLE		26. SUBJECT		27. DATE		28. BY	
29. TITLE		30. SUBJECT		31. DATE		32. BY	
33. TITLE		34. SUBJECT		35. DATE		36. BY	
37. TITLE		38. SUBJECT		39. DATE		40. BY	
41. TITLE		42. SUBJECT		43. DATE		44. BY	
45. TITLE		46. SUBJECT		47. DATE		48. BY	
49. TITLE		50. SUBJECT		51. DATE		52. BY	
53. TITLE		54. SUBJECT		55. DATE		56. BY	
57. TITLE		58. SUBJECT		59. DATE		60. BY	
61. TITLE		62. SUBJECT		63. DATE		64. BY	
65. TITLE		66. SUBJECT		67. DATE		68. BY	
69. TITLE		70. SUBJECT		71. DATE		72. BY	
73. TITLE		74. SUBJECT		75. DATE		76. BY	
77. TITLE		78. SUBJECT		79. DATE		80. BY	
81. TITLE		82. SUBJECT		83. DATE		84. BY	
85. TITLE		86. SUBJECT		87. DATE		88. BY	
89. TITLE		90. SUBJECT		91. DATE		92. BY	
93. TITLE		94. SUBJECT		95. DATE		96. BY	
97. TITLE		98. SUBJECT		99. DATE		100. BY	
101. TITLE		102. SUBJECT		103. DATE		104. BY	
105. TITLE		106. SUBJECT		107. DATE		108. BY	
109. TITLE		110. SUBJECT		111. DATE		112. BY	
113. TITLE		114. SUBJECT		115. DATE		116. BY	
117. TITLE		118. SUBJECT		119. DATE		120. BY	
121. TITLE		122. SUBJECT		123. DATE		124. BY	
125. TITLE		126. SUBJECT		127. DATE		128. BY	
129. TITLE		130. SUBJECT		131. DATE		132. BY	
133. TITLE		134. SUBJECT		135. DATE		136. BY	
137. TITLE		138. SUBJECT		139. DATE		140. BY	
141. TITLE		142. SUBJECT		143. DATE		144. BY	
145. TITLE		146. SUBJECT		147. DATE		148. BY	
149. TITLE		150. SUBJECT		151. DATE		152. BY	
153. TITLE		154. SUBJECT		155. DATE		156. BY	
157. TITLE		158. SUBJECT		159. DATE		160. BY	
161. TITLE		162. SUBJECT		163. DATE		164. BY	
165. TITLE		166. SUBJECT		167. DATE		168. BY	
169. TITLE		170. SUBJECT		171. DATE		172. BY	
173. TITLE		174. SUBJECT		175. DATE		176. BY	
177. TITLE		178. SUBJECT		179. DATE		180. BY	
181. TITLE		182. SUBJECT		183. DATE		184. BY	
185. TITLE		186. SUBJECT		187. DATE		188. BY	
189. TITLE		190. SUBJECT		191. DATE		192. BY	
193. TITLE		194. SUBJECT		195. DATE		196. BY	
197. TITLE		198. SUBJECT		199. DATE		200. BY	
201. TITLE		202. SUBJECT		203. DATE		204. BY	
205. TITLE		206. SUBJECT		207. DATE		208. BY	
209. TITLE		210. SUBJECT		211. DATE		212. BY	
213. TITLE		214. SUBJECT		215. DATE		216. BY	
217. TITLE		218. SUBJECT		219. DATE		220. BY	
221. TITLE		222. SUBJECT		223. DATE		224. BY	
225. TITLE		226. SUBJECT		227. DATE		228. BY	
229. TITLE		230. SUBJECT		231. DATE		232. BY	
233. TITLE		234. SUBJECT		235. DATE		236. BY	
237. TITLE		238. SUBJECT		239. DATE		240. BY	
241. TITLE		242. SUBJECT		243. DATE		244. BY	
245. TITLE		246. SUBJECT		247. DATE		248. BY	
249. TITLE		250. SUBJECT		251. DATE		252. BY	
253. TITLE		254. SUBJECT		255. DATE		256. BY	
257. TITLE		258. SUBJECT		259. DATE		260. BY	
261. TITLE		262. SUBJECT		263. DATE		264. BY	
265. TITLE		266. SUBJECT		267. DATE		268. BY	
269. TITLE		270. SUBJECT		271. DATE		272. BY	
273. TITLE		274. SUBJECT		275. DATE		276. BY	
277. TITLE		278. SUBJECT		279. DATE		280. BY	
281. TITLE		282. SUBJECT		283. DATE		284. BY	
285. TITLE		286. SUBJECT		287. DATE		288. BY	
289. TITLE		290. SUBJECT		291. DATE		292. BY	
293. TITLE		294. SUBJECT		295. DATE		296. BY	
297. TITLE		298. SUBJECT		299. DATE		300. BY	
301. TITLE		302. SUBJECT		303. DATE		304. BY	
305. TITLE		306. SUBJECT		307. DATE		308. BY	
309. TITLE		310. SUBJECT		311. DATE		312. BY	
313. TITLE		314. SUBJECT		315. DATE		316. BY	
317. TITLE		318. SUBJECT		319. DATE		320. BY	
321. TITLE		322. SUBJECT		323. DATE		324. BY	
325. TITLE		326. SUBJECT		327. DATE		328. BY	
329. TITLE		330. SUBJECT		331. DATE		332. BY	
333. TITLE		334. SUBJECT		335. DATE		336. BY	
337. TITLE		338. SUBJECT		339. DATE		340. BY	
341. TITLE		342. SUBJECT		343. DATE		344. BY	
345. TITLE		346. SUBJECT		347. DATE		348. BY	
349. TITLE		350. SUBJECT		351. DATE		352. BY	
353. TITLE		354. SUBJECT		355. DATE		356. BY	
357. TITLE		358. SUBJECT		359. DATE		360. BY	
361. TITLE		362. SUBJECT		363. DATE		364. BY	
365. TITLE		366. SUBJECT		367. DATE		368. BY	
369. TITLE		370. SUBJECT		371. DATE		372. BY	
373. TITLE		374. SUBJECT		375. DATE		376. BY	
377. TITLE		378. SUBJECT		379. DATE		380. BY	
381. TITLE		382. SUBJECT		383. DATE		384. BY	
385. TITLE		386. SUBJECT		387. DATE		388. BY	
389. TITLE		390. SUBJECT		391. DATE		392. BY	
393. TITLE		394. SUBJECT		395. DATE		396. BY	
397. TITLE		398. SUBJECT		399. DATE		400. BY	
401. TITLE		402. SUBJECT		403. DATE		404. BY	
405. TITLE		406. SUBJECT		407. DATE		408. BY	
409. TITLE		410. SUBJECT		411. DATE		412. BY	

**FLORIDA DEPARTMENT OF TRANSPORTATION
DISTRICT SEVEN RIGHT OF WAY COST ESTIMATE**

HDR#: 11573-025-096-25

255893 1	Former WPI#: N/A	District: Seven
Hillsborough	FAP No.: 2081-018P	Date: May 15, 2002
574	Alternate: Pond 4B	C.E. Sequence N/A
SR 574 PD&E Study from CR 579 to McIntosh Rd		

Gross	Net	Estimated Relocates:
0	0	Business 0
0	0	Residential 0
1	1	Signs 0
		Special 0
Parcels 1	1	Total Relocates 0

SUPPORT COSTS (PHASE 41)		Amount
Direct Labor Cost (Parcels 1 x 6,500 = Rate)		6,500
Direct Overhead (Parcels 1 x 0 = Rate)		0
TOTAL PHASE 41		\$6,500

COSTS (PHASE 4B)		Amount
Appraisal Fees Through Trial 1 Parcels x 12,000 =		12,000
Business Damage CPA Fees Through Trail 0 Claims x 19,000 =		0
Court Reporter & Process Servers 75% x 1 =		500
Expert Witness 75% x 1 =		30,000
Indicators 50% x 1 =		2,400
Demolition, Asb. Abate., Survey, etc. 0 Imprvmet x 15,000 =		0
Miscellaneous Contracts 1 Per Project x 15,000 =		15,000
Appraisal Fee Review 1 Parcels x 5,000 =		5,000
TOTAL PHASE 4B		\$64,900

AND COSTS (PHASE 43)		Amount	Subtotal
Land, Improvements & Severance Damages			
Cost to Cure Amount 0 x 130% * Design plan stage =		0	
Water Retention & Mtl. 129,125 x 130% (0 Parcels w/o R/W Acq)		167,863	
TOTAL			167,863
Admin. Settlements (Factor 0% x 0% of Line 15) =		0	
Litigation Awards (Factor 60% x 100% of Line 15) =		100,700	
Business Damages (Claims 0 x \$0) =		0	
Ins. Damages Incr (Factor 25% x \$ -) =		0	
Owner Appr. Fees (Parcels 1 x \$10,000) =		10,000	
Owner CPA Fees (Claims 0 x \$10,000) =		0	
Defend. Atty Fees (Sum of Lines 16, 17 & 19) 100,700 x 40% =		40,300	
Owner Expert Witne (Comm.+Unimp.) 0 + 1 = 18,000 =		18,000	
Other Condemn. Costs 1 x \$500 =		500	
TOTAL			169,500
TOTAL PHASE 43			\$337,400

High contingency for design plan stage:
 (1) PD&E plans - 130% (2) 30% plans - 125% (3) 60% plans - 120% (4) 90% plans - 115% (5) 268 Date - 110%

ACQUISITION CONSULTANT (PHASE 42)		Amount
Acquisition Consultant-50% of parcels \$20,000 x 1		20,000
TOTAL PHASE 42		\$20,000

ATION COSTS (PHASE 45)		Number	Amount
Replacement Housing			
Per \$20,000 x 0 =		0	
Ant \$10,000 x 0 =		0	
Move Costs			
Residential \$1,500 x 0 =		0	
Business/Farm \$20,000 x 0 =		0	
Personal Property \$2,000 x 0 =		\$0	
TOTAL PHASE 45			\$0

ation Services Cost \$0 (Not In Phase Total)		
(All Phases) TOTAL ESTIMATE		\$428,800

Daniel Trosper	Signed: <i>[Signature]</i>	Date: 5/15/02
N/A	Signed: _____	Date: _____
N/A	Signed: _____	Date: _____
view: Marilyn Jackson	Signed: <i>[Signature]</i>	Date: 5/15/02

ate Sequence #: _____ Dated: _____ In the Amount of \$ _____ Data Input Completion Date: _____

Administrative settlements and litigation awards have been changed to reflect one ownership. Administrative settlements are considered to be zero, while litigation is factored at 60% of land and improvement value.

g indicates the estimator's confidence in the above estimate:	Future Value Factors @	10%
Type A - indicates the most confidence	Year One	1.1000
Type B - indicates above average confidence	Year Two	1.2100
Type C - indicates below average confidence	Year Three	1.3310
Type D - indicates the least or no confidence	Year Four	1.4641
	Year Five	1.6105

Indicates the Department's purpose for this estimate:
 Update: _____ Gaming 1: _____ Special Purpose: ☒ Docs to RW: _____

**FLORIDA DEPARTMENT OF TRANSPORTATION
DISTRICT SEVEN RIGHT OF WAY COST ESTIMATE**

HDR#: 11573-025-096-25

255893 1	Former WPI#: N/A	District: Seven
Hillsborough	FAP No.: 2081-018P	Date: 15-May-02
574	Alternate: Pond 5A	C.E. Sequence N/A
Des. SR 574 PD&E Study from CR 579 to McIntosh Rd		

Gross	Net	Estimated Relocates:
0	0	Business
4	2	Residential
0	0	Signs
		Special
4	2	Total Relocates

SUPPORT COSTS (PHASE 41)				Amount
Direct Labor Cost	(Parcels)	2	x 6,500 =	Rate) 13,000
Direct Overhead	(Parcels)	2	x 0 =	Rate) 0
TOTAL PHASE 41				\$13,000

PS (PHASE 4B)				Amount
Appraisal Fees Through Trail	2	Parcels	x 12,000 =	24,000
Business Damage CPA Fees Through Trail	0	Claims	x 19,000 =	0
Expert Reporter & Process Servers	75%	x 2 =	2	Parcels x 500 = 1,000
Expert Witness	75%	x 2 =	2	Parcels x 30,000 = 60,000
Mediators	50%	x 2 =	1	Parcels x 2,400 = 2,400
Demolition, Asb. Abate., Survey, etc.		4	Imprvmet x 15,000 =	60,000
Miscellaneous Contracts		1	Per Project x 15,000 =	15,000
Appraisal Fee Review		1	Parcels x 5,000 =	5,000
TOTAL PHASE 4B				\$167,400

AND COSTS (PHASE 43)				Amount	Subtotal
Land, Improvements & Severance Damages					
Land Cost to Cure Amount	0	x 130% * Design plan stage =	0		
Water Retention & Mtl.	497,900	x 130% (0 Parcels w/o R/W Acq)	647,270		
				(Lines 13 & 14)	647,270
Admin. Settlements (Factor	45%	x 30% of Line 15)	=	87,400	
Litigation Awards (Factor	60%	x 70% of Line 15)	=	271,900	
Business Damages (Claims	0	x \$0)	=	0	
Business Damages Incr (Factor	25%	x \$ -)	=	0	
Owner Appr. Fees (Parcels	2	x \$10,000)	=	20,000	
Owner CPA Fees (Claims	0	x \$10,000)	=	0	
Defend. Atty Fees (Sum of Lines 16, 17 & 19)	359,300	x 40%)	=	143,700	
Owner Expert Witne (Comm.+Unimp.)	0	+ 0) 18,000	=	0	
Other Condemn. Costs	2	x \$500	=	1,000	
				(Lines 16 thru 24)	524,000
TOTAL PHASE 43				\$1,171,300	

Design contingency for design plan stage:
 (1) PD&E plans - 130% (2) 30% plans - 125% (3) 60% plans - 120% (4) 90% plans - 115% (5) 268 Date - 110%

ACQUISITION CONSULTANT (PHASE 42)			
Acquisition Consultant-50% of parcels	\$20,000	x 1	TOTAL PHASE 42
			\$20,000

ATION COSTS (PHASE 45)			
Replacement Housing	Number	Amount	
Per	2	=	40,000
Ant	2	=	40,000
Move Costs			
Residential	4	=	26,000
Business/Farm	0	=	0
Personal Property	1	=	\$2,000
Lines 28 thru 32)			
Relocation Services Cost	\$10,800	(Not in Phase Total)	
TOTAL PHASE 45			
\$108,000			

(All Phases)	TOTAL ESTIMATE	\$1,479,700
--------------	-----------------------	--------------------

Daniel Trosper	Signed:	<i>Daniel Trosper</i>	Date:	5/15/02
N/A	Signed:		Date:	
Daniel Trosper	Signed:	<i>Marilyn Jackson</i>	Date:	5/15/02
view: Marilyn Jackson	Signed:		Date:	

ate Sequence #: Dated: In the Amount of \$ Data Input Completion Date:

Ownership lines did not match up with County plat maps. Assumptions were made in order to ensure consistency with County records. Parcel 103 is not just a long rectangular parcel, but has extensive frontage on SR 574. The property immediately to the east of Parcel 103, on Oliveira St., has no frontage on SR 574 as the map depicts, but is a small residential lot.

This estimate had two parcels which were not included in the main parcel count. Two parcels had low income housing which required a \$20,000 increase in relocation costs on line 30.

Indicates the estimator's confidence in the above estimate:	Future Value Factors @	10%
Type A - Indicates the most confidence	Year One	1.1000
Type B - Indicates above average confidence	Year Two	1.2100
Type C - Indicates below average confidence	Year Three	1.3310
Type D - Indicates the least or no confidence	Year Four	1.4641
	Year Five	1.6105

Indicates the Department's purpose for this estimate:
 Update: Gaming 1: Special Purpose: X Docs to RW:

PRELIMINARY

SUBJECT TO CHANGE

PART TO		1200 VAD TO 2000 VAD	
DATE	TIME	LOCATION	REMARKS
10/10/01	10:00	1000	1000
10/10/01	10:05	1005	1005
10/10/01	10:10	1010	1010
10/10/01	10:15	1015	1015
10/10/01	10:20	1020	1020
10/10/01	10:25	1025	1025
10/10/01	10:30	1030	1030
10/10/01	10:35	1035	1035
10/10/01	10:40	1040	1040
10/10/01	10:45	1045	1045
10/10/01	10:50	1050	1050
10/10/01	10:55	1055	1055
10/10/01	11:00	1100	1100
10/10/01	11:05	1105	1105
10/10/01	11:10	1110	1110
10/10/01	11:15	1115	1115
10/10/01	11:20	1120	1120
10/10/01	11:25	1125	1125
10/10/01	11:30	1130	1130
10/10/01	11:35	1135	1135
10/10/01	11:40	1140	1140
10/10/01	11:45	1145	1145
10/10/01	11:50	1150	1150
10/10/01	11:55	1155	1155
10/10/01	12:00	1200	1200
10/10/01	12:05	1205	1205
10/10/01	12:10	1210	1210
10/10/01	12:15	1215	1215
10/10/01	12:20	1220	1220
10/10/01	12:25	1225	1225
10/10/01	12:30	1230	1230
10/10/01	12:35	1235	1235
10/10/01	12:40	1240	1240
10/10/01	12:45	1245	1245
10/10/01	12:50	1250	1250
10/10/01	12:55	1255	1255
10/10/01	13:00	1300	1300
10/10/01	13:05	1305	1305
10/10/01	13:10	1310	1310
10/10/01	13:15	1315	1315
10/10/01	13:20	1320	1320
10/10/01	13:25	1325	1325
10/10/01	13:30	1330	1330
10/10/01	13:35	1335	1335
10/10/01	13:40	1340	1340
10/10/01	13:45	1345	1345
10/10/01	13:50	1350	1350
10/10/01	13:55	1355	1355
10/10/01	14:00	1400	1400
10/10/01	14:05	1405	1405
10/10/01	14:10	1410	1410
10/10/01	14:15	1415	1415
10/10/01	14:20	1420	1420
10/10/01	14:25	1425	1425
10/10/01	14:30	1430	1430
10/10/01	14:35	1435	1435
10/10/01	14:40	1440	1440
10/10/01	14:45	1445	1445
10/10/01	14:50	1450	1450
10/10/01	14:55	1455	1455
10/10/01	15:00	1500	1500
10/10/01	15:05	1505	1505
10/10/01	15:10	1510	1510
10/10/01	15:15	1515	1515
10/10/01	15:20	1520	1520
10/10/01	15:25	1525	1525
10/10/01	15:30	1530	1530
10/10/01	15:35	1535	1535
10/10/01	15:40	1540	1540
10/10/01	15:45	1545	1545
10/10/01	15:50	1550	1550
10/10/01	15:55	1555	1555
10/10/01	16:00	1600	1600
10/10/01	16:05	1605	1605
10/10/01	16:10	1610	1610
10/10/01	16:15	1615	1615
10/10/01	16:20	1620	1620
10/10/01	16:25	1625	1625
10/10/01	16:30	1630	1630
10/10/01	16:35	1635	1635
10/10/01	16:40	1640	1640
10/10/01	16:45	1645	1645
10/10/01	16:50	1650	1650
10/10/01	16:55	1655	1655
10/10/01	17:00	1700	1700
10/10/01	17:05	1705	1705
10/10/01	17:10	1710	1710
10/10/01	17:15	1715	1715
10/10/01	17:20	1720	1720
10/10/01	17:25	1725	1725
10/10/01	17:30	1730	1730
10/10/01	17:35	1735	1735
10/10/01	17:40	1740	1740
10/10/01	17:45	1745	1745
10/10/01	17:50	1750	1750
10/10/01	17:55	1755	1755
10/10/01	18:00	1800	1800
10/10/01	18:05	1805	1805
10/10/01	18:10	1810	1810
10/10/01	18:15	1815	1815
10/10/01	18:20	1820	1820
10/10/01	18:25	1825	1825
10/10/01	18:30	1830	1830
10/10/01	18:35	1835	1835
10/10/01	18:40	1840	1840
10/10/01	18:45	1845	1845
10/10/01	18:50	1850	1850
10/10/01	18:55	1855	1855
10/10/01	19:00	1900	1900
10/10/01	19:05	1905	1905
10/10/01	19:10	1910	1910
10/10/01	19:15	1915	1915
10/10/01	19:20	1920	1920
10/10/01	19:25	1925	1925
10/10/01	19:30	1930	1930
10/10/01	19:35	1935	1935
10/10/01	19:40	1940	1940
10/10/01	19:45	1945	1945
10/10/01	19:50	1950	1950
10/10/01	19:55	1955	1955
10/10/01	20:00	2000	2000
10/10/01	20:05	2005	2005
10/10/01	20:10	2010	2010
10/10/01	20:15	2015	2015
10/10/01	20:20	2020	2020
10/10/01	20:25	2025	2025
10/10/01	20:30	2030	2030
10/10/01	20:35	2035	2035
10/10/01	20:40	2040	2040
10/10/01	20:45	2045	2045
10/10/01	20:50	2050	2050
10/10/01	20:55	2055	2055
10/10/01	21:00	2100	2100
10/10/01	21:05	2105	2105
10/10/01	21:10	2110	2110
10/10/01	21:15	2115	2115
10/10/01	21:20	2120	2120
10/10/01	21:25	2125	2125
10/10/01	21:30	2130	2130
10/10/01	21:35	2135	2135
10/10/01	21:40	2140	2140
10/10/01	21:45	2145	2145
10/10/01	21:50	2150	2150
10/10/01	21:55	2155	2155
10/10/01	22:00	2200	2200
10/10/01	22:05	2205	2205
10/10/01	22:10	2210	2210
10/10/01	22:15	2215	2215
10/10/01	22:20	2220	2220
10/10/01	22:25	2225	2225
10/10/01	22:30	2230	2230
10/10/01	22:35	2235	2235
10/10/01	22:40	2240	2240
10/10/01	22:45	2245	2245
10/10/01	22:50	2250	2250
10/10/01	22:55	2255	2255
10/10/01	23:00	2300	2300
10/10/01	23:05	2305	2305
10/10/01	23:10	2310	2310
10/10/01	23:15	2315	2315
10/10/01	23:20	2320	2320
10/10/01	23:25	2325	2325
10/10/01	23:30	2330	2330
10/10/01	23:35	2335	2335
10/10/01	23:40	2340	2340
10/10/01	23:45	2345	2345
10/10/01	23:50	2350	2350
10/10/01	23:55	2355	2355
10/10/01	24:00	2400	2400

**FLORIDA DEPARTMENT OF TRANSPORTATION
DISTRICT SEVEN RIGHT OF WAY COST ESTIMATE**

HDR#: 11573-025-096-25

255893 1	Former WPI#:	N/A	District:	Seven
Hillsborough	FAP No.:	2081-018P	Date:	15-May-02
574'	Alternate:	Pond 5B	C.E. Sequence	N/A
Des. SR 574 PD&E Study from CR 579 to McIntosh Rd				

Gross	Net	Estimated Relocates:
1	0	Business
3	2	Residential
0	0	Signs
		Special
4	2	Total Relocates

SUPPORT COSTS (PHASE 41)				Amount
Direct Labor Cost	(Parcels	2	x	6,500 = Rate)
Direct Overhead	(Parcels	2	x	0 = Rate)
				13,000
				0
TOTAL PHASE 41				\$13,000

PS (PHASE 4B)				Amount
Appraisal Fees Through Trail		2	Parcels x	12,000 = 24,000
Business Damage CPA Fees Through Trail		0	Claims x	19,000 = 0
Court Reporter & Process Servers	75%	x	2 =	2 Parcels x 500 = 1,000
Expert Witness	75%	x	2 =	2 Parcels x 30,000 = 60,000
Mediators	50%	x	2 =	1 Parcels x 2,400 = 2,400
Demolition, Asb. Abate., Survey, etc.		2	Imprvmet x	15,000 = 30,000
Miscellaneous Contracts		1	Per Project x	15,000 = 15,000
Appraisal Fee Review		1	Parcels x	5,000 = 5,000
TOTAL PHASE 4B				\$137,400

LAND COSTS (PHASE 43)				Amount	Subtotal
Land, Improvements & Severance Damages					
Cost to Cure Amount	0	x	130% * Design plan stage =	0	
Water Retention & Mit.	339,728	x	130% (0 Parcels w/o R/W Acq)	441,644	
				(Lines 13 & 14)	441,644
Admin. Settlements (Factor	45%	x	30% of Line 15)	59,800	
igation Awards (Factor	60%	x	70% of Line 15)	185,500	
Business Damages (Claims	0	x	\$0)	0	
s. Damages Incr (Factor	25%	x	\$ -)	0	
Owner Appr. Fees (Parcels	2	x	\$10,000)	20,000	
Owner CPA Fees (Claims	0	x	\$10,000)	0	
Attend. Atty Fees (Sum of Lines 16, 17 & 19)	245,100	x	40%)	98,000	
Owner Expert Witne (Comm.+Unimp.)	0	+	0)	18,000	
Owner Condemn. Costs	2	x	\$500	1,000	
TOTAL PHASE 43				\$805,700	

Design contingency for design plan stage:
(1) PD&E plans - 130% (2) 30% plans - 125% (3) 60% plans - 120% (4) 90% plans - 115% (5) 268 Date - 110%

ACQUISITION CONSULTANT (PHASE 42)			
Acquisition Consultant-50% of parcels	\$20,000	x	1
			TOTAL PHASE 42
			\$20,000

RELATION COSTS (PHASE 45)			
Replacement Housing		Number	Amount
er	\$20,000	x	2 = 40,000
nt	\$10,000	x	0 = 0
Move Costs			
idential	\$1,500	x	2 = 3,000
ness/Farm	\$20,000	x	0 = 0
onal Property	\$2,000	x	2 = \$4,000
			TOTAL PHASE 45
			\$47,000

ation Services Cost	\$4,700	(Not in Phase Total)
TOTAL ESTIMATE		
\$1,023,100		

Daniel Trosper	Signed:	<i>Daniel Trosper</i>	Date:	5/15/02
N/A	Signed:		Date:	
Daniel Trosper	Signed:	<i>Marilyn Jackson</i>	Date:	5/15/02
iew: Marilyn Jackson	Signed:		Date:	

ite Sequence #: Dated: In the Amount of \$ Data Input Completion Date:

Ownership lines did not match up with County plat maps. Assumptions were made to ensure consistency with County records. Parcel 102 is larger than is depicted, extending approximately 100 feet farther west on SR 574. The residential lot immediately to the west on Oliveira St. is shifted further west. The next property to the west has no frontage on SR 574, as the map depicts, but is a small residential lot. This estimate had 2 parcels which had mainline takings and which were not included in the net parcel count. Parcel 102 is damaged out in the mainline taking.

Indicates the estimator's confidence in the above estimate:	Future Value Factors @	10%
Type A - Indicates the most confidence	Year One	1.1000
Type B - Indicates above average confidence	Year Two	1.2100
Type C - Indicates below average confidence	Year Three	1.3310
Type D - Indicates the least or no confidence	Year Four	1.4641
	Year Five	1.6105

Indicates the Department's purpose for this estimate:
Update: Gaming 1: Special Purpose: X Docs to RW:

**FLORIDA DEPARTMENT OF TRANSPORTATION
DISTRICT SEVEN RIGHT OF WAY COST ESTIMATE**

HDR#: 11573-025-096-25

255893 1	Former WPI#:	N/A	District:	Seven
Hillsborough	FAP No.:	2081-018P	Date:	15-May-02
574	Alternate:	Pond 1A	C.E. Sequence	N/A
SR 574 PD&E Study from CR 579 to McIntosh Rd				

Gross	Net	Estimated Relocates:
0	0	Business
1	0	Residential
0	0	Signs
		Special
1	0	Total Relocates

PORT COSTS (PHASE 41)		Amount
Labor Cost	(Parcels 0 x 0,590 = Rate)	0
Overhead	(Parcels 0 x 0 = Rate)	0
TOTAL PHASE 41		\$0

(PHASE 4B)		Amount
Assessment Fees Through Trial	0 Parcels x 12,000 =	0
Business Damage CPA Fees Through Trial	0 Claims x 19,000 =	0
Reporter & Process Servers	0 Parcels x 500 =	0
Witness	0 Parcels x 30,000 =	0
Attorneys	0 Parcels x 2,400 =	0
Location, Ass. Abate., Survey, etc.	2 Improvmet x 15,000 =	30,000
Collateral Contracts	1 Per Project x 15,000 =	15,000
Assessment Fee Review	0 Parcels x 5,000 =	0
TOTAL PHASE 4B		\$45,000

AD COSTS (PHASE 43)		Amount	Subtotal
Improvements & Severance Damages			
Cost to Cure Amount	0 x 130% * Design plan stage =	0	
Retention & Mtl.	851,927 x 130% (0 Parcels w/o R/W Acq)	1,107,505	
TOTAL	(Lines 13 & 14)		1,107,505
In. Settlements (Factor	0% x 0% of Line 15)	=	0
ation Awards (Factor	60% x 100% of Line 15)	=	664,500
Business Damages (Claims	0 x \$0)	=	0
Damages Incr (Factor	25% x \$ -)	=	0
er Appr. Fees (Parcels	0 x \$10,000)	=	0
er CPA Fees (Claims	0 x \$10,000)	=	0
nd. Atty Fees (Sum of Lines 16, 17 & 19)	664,500 x 40%	=	265,800
er Expert Witne (Comm.+Unimp.)	0 + 0 = 18,000	=	0
er Condemn. Costs	0 x \$500	=	0
TOTAL	(Lines 16 thru 24)		930,300
TOTAL PHASE 43			\$2,037,800

contingency for design plan stage:
PD&E plans - 130% (2) 30% plans - 125% (3) 60% plans - 120% (4) 90% plans - 115% (5) 268 Date - 110%

ACQUISITION CONSULTANT (PHASE 42)		Amount
Acquisition Consultant-50% of parcels	\$20,000 x 0	0
TOTAL PHASE 42		\$0

RELOCATION COSTS (PHASE 45)		Number	Amount
Replacement Housing			
er	\$20,000 x 1 =	20,000	
nt	\$10,000 x 2 =	20,000	
Move Costs			
ential	\$1,500 x 3 =	4,500	
ess/Farm	\$20,000 x 0 =	0	
nal Property	\$2,000 x 1 =	2,000	
TOTAL PHASE 45			\$46,500
ation Services Cost		\$4,650 (Not In Phase Total)	

(All Phases)	TOTAL ESTIMATE	\$2,129,300
--------------	-----------------------	--------------------

Daniel Trosper	Signed:	<i>Daniel Trosper</i>	Date:	5/15/02
N/A	Signed:		Date:	
Daniel Trosper	Signed:	<i>Daniel Trosper</i>	Date:	5/15/02
iew: Marilyn Jackson	Signed:	<i>Marilyn Jackson</i>	Date:	5/15/02

ite Sequence #: Dated: In the Amount of \$ Data Input Completion Date:

Public records show 108,900 square feet for the parent tract. This number was relied on for the worst case scenario
The parcel was counted in the mainline estimate.

Indicates the estimator's confidence in the above estimate:	Future Value Factors @	10%
Type A - Indicates the most confidence	Year One	1.1000
Type B - Indicates above average confidence	Year Two	1.2100
Type C - Indicates below average confidence	Year Three	1.3310
Type D - Indicates the least or no confidence	Year Four	1.4641
	Year Five	1.6105

Indicates the Department's purpose for this estimate:
Update: Gaming 1: Special Purpose: X Docs to RW:

WAL-MART / PUBLICIX / WALGREENS
BEALLS OUTLET SHOPPING CENTER

DISCOUNT
AUTO
PARTS

HIGHVIEW ROAD

BRANDON
AUTO-PAINT
& BODY SHOP

B-1

VALUE PAWN

C&J AUTO SALES

A-OK
INSURANCE

STORAGE AREA

PRIVATE RESIDENCE

POND SITE





300

POT STA. 300+08.11

SEGMENT "A"

5-LANE URRAN TYPICAL SECTION








SEGMENT "A"

5-LANE URBAN TYPICAL SECTION





METRO STORAGE UNITS

VACANT

PT STA 368+54.57

365

370

MARTIN LUTHER KING JR. BLVD.

CSX R.R.

LEGEND

- PROPOSED RIGHT OF WAY
- EXISTING RIGHT OF WAY
- PROPOSED EDGE OF PAVEMENT
- PROPERTY LINE
- WETLAND BOUNDARY
- POTENTIAL POND SITE
- POTENTIAL BUSINESS RELOCATION
- POTENTIAL RESIDENTIAL RELOCATION
- ▲ POTENTIAL CONTAMINATION SITE
- Ⓜ POTENTIAL HISTORIC SITE
- Ⓢ EXISTING TRAFFIC SIGNAL


ELITE POOL
& SPA

BUCK'S PLUMBING
SUPPLY

MATCH LINE
(SEE SHEET (10) 8)

TED'S SEPTIC
TANKS














SEGMENT "C"


4-LANE SUBURBAN TYPICAL SECTION

1900

1900


1900












1900



SEGMENT "C"

4-LANE SUBURBAN TYPICAL SECTION





-  PROPOSED RIGHT OF WAY
-  EXISTING RIGHT OF WAY
-  PROPOSED EDGE OF PAVEMENT
-  PROPERTY LINE
-  WETLAND BOUNDARY
-  POTENTIAL POND SITE
-  POTENTIAL BUSINESS RELOCATION
-  POTENTIAL RESIDENTIAL RELOCATION
-  POTENTIAL CONTAMINATION SITE
-  POTENTIAL HISTORIC SITE
-  EXISTING TRAFFIC SIGNAL



SEGMENT "C"


4-LANE SUBURBAN TYPICAL SECTION





SEGMENT "C"

4-LANE SUBURBAN TYPICAL SECTION



SEGMENT "C"


4-LANE SUBURBAN TYPICAL SECTION











LEGEND

	PROPOSED RIGHT OF WAY
	EXISTING RIGHT OF WAY
	PROPOSED EDGE OF PAVEMENT
	PROPERTY LINE
	WETLAND BOUNDARY
	POTENTIAL POND SITE
	POTENTIAL BUSINESS RELOCATION
	POTENTIAL RESIDENTIAL RELOCATION
	POTENTIAL CONTAMINATION SITE
	POTENTIAL HISTORIC SITE
	EXISTING TRAFFIC SIGNAL

